MEADOW POINTE TRACT 2
PARCELS 1, 2, 3 &4

Preliminary Plan and Site Construction Plans

PASCO COUNTY, FLORIDA





VICINITY MAP
PASCO COUNTY, FLORIDA
SECTION 31, TOWNSHIP 26 SOUTH, RANGE 20 EAST

(Taken from Title Commitment No. NCS-1217091-ALT with a date of April 15, 2024 7:30 AM)

DESCRIPTION:

The Land referred to herein below is situated in the County of Pasco, State of Florida, and is described as follows:

PARCEL 1:

PARCELS 1, 3 AND 4, AND TRACT B, MEADOW POINTE TRACT 2, ACCORDING TO THE PLAT THEREOF, RECORDED IN PLAT BOOK 68, PAGES 99 THROUGH 103, INCLUSIVE, PUBLIC RECORDS OF PASCO COUNTY, FLORIDA.

PARCEL 2:

A PARCEL OF LAND LYING IN SECTION 31, TOWNSHIP 26 SOUTH, RANGE 20 EAST, PASCO COUNTY, FLORIDA, BEING FURTHER DESCRIBED AS FOLLOWS:

COMMENCE AT THE NORTHWEST CORNER OF SAID SECTION 31; THENCE SOUTH 89°58' 03" EAST, 101.26 FEET TO A POINT ON THE EAST RIGHT-OF-WAY LINE OF COUNTY ROAD NO. 581; THENCE SOUTH 00°30' 15" WEST, ALONG SAID EAST RIGHT-OF-WAY LINE, 2916.54 FEET TO THE POINT OF BEGINNING; THENCE SOUTH 89°29' 45" EAST, 264.26 FEET; THENCE SOUTH 00°30' 15" WEST, 20.67 FEET; THENCE SOUTH 89°29' 45" EAST, 63.33 FEET; THENCE SOUTH 00°30' 15" WEST, 299.67 FEET; THENCE NORTH 89°29' 45" WEST, 327.59 FEET; THENCE ALONG SAID EAST RIGHT-OF-WAY LINE NORTH 00°30' 15" EAST, 320.34 FEET TO THE POINT OF BEGINNING.

LESS AND EXCEPT:

A PARCEL OF LAND LYING IN SECTION 31, TOWNSHIP 26 SOUTH, RANGE 20 EAST, PASCO COUNTY, FLORIDA, BEING FURTHER DESCRIBED AS FOLLOWS:

COMMENCE AT THE NORTHWEST CORNER OF SAID SECTION 31; THENCE SOUTH 89°58' 03" EAST, 101.26 FEET TO A POINT ON THE EAST RIGHT-OF-WAY LINE OF COUNTY LINE ROAD, AS RECORDED IN OFFICIAL RECORDS BOOK 123, PAGE 653, OF THE PUBLIC RECORDS OF PASCO COUNTY, FLORIDA; THENCE ALONG SAID EAST RIGHT-OF-WAY LINE OF COUNTY LINE ROAD, SOUTH 00°30' 15" WEST, 2916.54 FEET TO THE POINT OF BEGINNING; THENCE SOUTH 89°29' 45" EAST, 20.00 FEET; THENCE ALONG A LINE LYING 20.00 FEET EASTERLY OF AND PARALLEL WITH THE AFORESAID EAST RIGHT-OF-WAY LINE OF COUNTY LINE ROAD, SOUTH 00°30' 15" WEST, 320.34 FEET; THENCE NORTH 89°29' 45" WEST, 20.00 FEET TO A POINT ON THE AFORESAID EAST RIGHT-OF-WAY LINE OF COUNTY LINE ROAD; THENCE ALONG SAID EAST RIGHT-OF-WAY LINE OF COUNTY LINE ROAD, NORTH 00°30' 15" EAST, 320.34 FEET TO THE POINT OF BEGINNING.

Benchmark:
Elevations shown hereon are based on the North American Vertical Datum of 1988 (NAVD 88) based on Tampa Bay Water Benchmark Stamped "CYB 8787", having a published elevation of 54.69 feet (NAVD 88).

Flood Note:
The subject parcel lies in Flood Zones "AE" & "X", according to Flood Insurance Rate Map, Map No. 12101C0436F for Pasco County, Community No. 120230, Pasco County, Florida, dated September 26, 2014

INDEX OF CONSTRUCTION PLANS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	GENERAL NOTES
3	DEMOLITION PLAN
4	PRELIMINARY PLAN
5	PAVEMENT SECTIONS AND DETAILS
6	GRADING AND DRAINAGE PLAN
7	STRUCTURE DATA & CONTROL STRUCTURE DETAIL
8-9	CROSS SECTIONS
10	BRUCE B. DOWNS TURN LANES
11	BRUCE B. DOWNS SECTIONS
12	SIDEWALK, SIGNING, & PAVEMENT MARKING PLAN
13	SIDEWALK DETAILS
14-16	DRAINAGE DETAILS
17	DUMPSTER ENCLOSURE DETAILS
18	WATER AND SEWER PLAN
19	POTABLE WATER SYSTEM DETAILS
20	SANITARY SEWER SYSTEM DETAILS
21	DRAINAGE AREA MAP
L1-*	LANDSCAPE PLAN
1 of 1	PROPERTY OWNERSHIP AND EASEMENT MAP
1 of 1	SHARED SITE COSTS MAP

PERMIT / FILE NOS.	
SITE ADDRESS	1410 Bruce B Downs Blvd. 33544
WATER COMMITMENT	
SEWER COMMITMENT	
SWFWMD	
WATER DEP	
SEWER DEP	
PARCEL ID NO.	31 26 20 0230 00000 0030, 31 26 20 0000 00100 0044, 31-26-20-0230-00000-0010, 31 26 20 0230 00000 0040, 31-26-20-0230-00B00-0000
RZ#	
DEVELOPMENT REVIEW	PREAPP 2024 0021

Prepared For:

SJC Ventures
1115 Howell Mill Rd., Suite 777
Atlanta, GA 30318

Know what's **below.** **Call** before you dig.

David G. Fuxan
Digitally signed by David G. Fuxan
Date: 2025.02.11 15:58:13 -05'00'

FLORIDA LICENSED PROFESSIONAL ENGINEER No. 33133 STATE OF FLORIDA

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	SHEET NO.	BY

REVISIONS

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194
email: dfuxan@fuxaneng.com
Engineering Business Certificate of Authorization No.: 26548

DAVID G. FUXAN FLORIDA PROFESSIONAL ENGINEER 33133

DATE: 2-9-2025 JOB NO. 2025-MP2-01

Elevations based on North American Vertical Datum 1988 (NAVD 88)
Conversion from NAVD 88 to NGVD 29 = +0.82 Feet

DESIGNED BY: FUXAN DRAWN BY: MIDDLETON

FILE: CV

STORM WATER POLLUTION PREVENTION PLAN

Contained on these plans and within the following notes is a Storm Water Pollution Prevention Plan (SWPPP) which has been developed by Fuxan Engineering, Inc. in accordance with the Florida Department of Environmental Protection's (FDEP) "National Pollutant Discharge Elimination System" (NPDES) Generic Permit for Stormwater Discharge from Large and Small Construction Activities.

The following entities are identified as team members of "SWPPP": Fuxan Engineering, Inc., the Developer as identified in the title box of these plans, and the site contractor and his sub-contractors. Each team member has specific responsibilities and obligations. In general, all team members, with regard to their involvement and responsibilities on the project, are to implement all necessary storm water management controls to assure compliance with the NPDES Generic Permit for Storm Water Discharges from Construction Activities, the Southwest Florida Water Management District Permit, the applicable local governing agency (i.e. Hillsborough County, City of Tampa, etc) and the guidelines listed in the SWPPP. The duties and responsibilities of the team members as they pertain to the SWPPP are as follows:

Fuxan Engineering, Inc.

A. Develop SWPPP including, but not limited to, retention/detention ponds, control structures, erosion control methods and locations and stabilization criteria. This design is included within these construction plans and the following notes and instructions.

B. Submit and obtain the necessary design related storm water permits from the Florida Department of Environmental Protection, the Southwest Florida Water Management District and other applicable governmental bodies.

C. Submit to SWFWMD and the operator of the municipal separate storm water system, if applicable, a letter of construction commencement.

Contractor

A. Sign and return to Fuxan a Contractors Certification Form certifying your understanding of and willingness to comply with the Storm Water Pollution Prevention Plan no later than 48 hours prior to commencement of construction. Also, each subcontractor affected by the SWPPP must certify to the contractor that they understand and shall comply with the NPDES permit and SWPPP. A record of these certifications shall be maintained by the contractor on site.

B. Submit notice of intent to the FDEP. Prepare Dewatering Plan. During construction, assure compliance with the designed Storm Water Pollution Prevention Plans prepared by Fuxan Engineering, Inc. and the NPDES Generic Permit for Storm Water Discharges from Large and Small Construction Activities.

C. Maintain a copy of the construction plans, which include the Storm Water Pollution Prevention Plan,the NOI, and all inspection reports and certifications on site.

D. Undertake all reasonable Best Management Practices (BMP's) to assure that silted or otherwise polluted storm water is not allowed to discharge from the site during all phases of construction. Stabilization BMP's that may be used include: temporary or per manent seeding, mulching, geotextiles, sodding, vegetative buffer strips, protection of trees and preservation of mature vegetation. Structural erosion and sediment control BMP's that may be used include: straw bale dikes, silt fences, earth dikes, brush barriers, drainage swales, check dams, subsurface drain, pipe slope drain, level spreaders, storm drain inlet protection, outlet protection, sediment traps, and temporary sediment basins. Detention ponds may also be used as temporary sediment basins. Additional BMP's that may need to be implemented include: providing protected storage areas for chemicals, paints, solvents, fertilizers, and other potentially toxic materials. Providing waste receptacles at convenient locations and providing regular collection of wastes, including building material wastes. Minimizing of-site tracking of sediments. Making adequate preparations, including training and equipment to contain spills of oil and hazardous materials. Complying with applicable state or local waste disposal, sanitary sewer or septic system regulations and the use of appropriate pollution prevention measures for allowable non-storm water components of discharge.

E. Notify Fuxan Engineering, Inc. and the developer in writing of any non-storm water pollution sources which are being stored, or otherwise used during the construction of the project, i.e., fertilizers, fuels, pesticides, other chemicals. This notification should be accompanied with the contractor's design and methods to prevent pollution run-off from these sources.

F. Develop a maintenance and inspection plan which includes, but is not limited to the following:

A. The specific areas to be inspected and maintained that includes all the disturbed areas and material storage areas of the site.

B. The erosion and sediment controls identified in the SWPPP to be maintained and inspected and those additional controls that the contractor deems necessary.

C. Maintenance procedures.

D. The procedure to follow if additional work is required or whom to call.

E. Inspections and maintenance forms.

F. The personnel assigned to each task.

The following shall be inspected a minimum of once a week or within 24 hours after 0.50 inches of rainfall:

Stabilization measures (once a month if fully stabilized).

Structural controls.

Discharge points.

Construction entrances and exits.

Areas used for storage of exposed materials.

An inspection form shall be completed for each inspection. Any permit violations should be noted and corrective measures shall be taken no later than 7 days after the inspection occurred. If revisions to the SWPPP are needed, a report form for changes in the SWPPP shall be completed and a copy sent to Fuxan Engineering, Inc. The original shall be kept on-site as documentation of the change. If the inspection passes, a certification that the facility is in compliance with the SWPPP and the NPDES permit must be signed by a duly authorized representative of the principal executive official of the operator of the SWPPP with one of the following qualifications:

1. Has successfully completed the Florida Stormwater, Erosion and Sediment Control Inspector Training Program.
2. Successfully completed a similar training program.
3. Has enough practical on the job training to be qualified to perform the inspections.

Retain inspection reports and certifications for at least three years.

G. Site stabilization measures shall be initiated as soon as practical but in no case more than 7 days, in portions of the site where construction activities have temporarily or permanently ceased.

H. Releases in Excess of Reportable Quantities.

1. The discharge of hazardous substances or oil in the stormwater discharge(s) from a facility or activity shall be prevented or minimized in accordance with the applicable stormwater pollution prevention plan for the facility or activity. This permit does not relieve the operator of the reporting requirements of 40 CFR part 117 and 40 CFR part 302. Where a release containing a hazardous substance in an amount equal to or in excess of a reporting quantity established under either 40 CFR 117 or 40 CFR 302, occurs during a 24 hour period:

   a. The operator is required to notify the State Warning Point (800-210-0519 or 850-413-9911) as soon as he or she has knowledge of the discharge;

   b. The operator shall submit within 14 calendar days of knowledge of the release a written description of: the release (including the type and estimate of the amount of material released), the date that such release occurred, the circumstances leading to the release, and remedial steps to be taken, to the Florida Department of Environmental Protection, NPDES Stormwater Section, Mail Station 2500, 2600 Blair Stone Road, Tallahassee, Florida 32399-2400; and

   c. The stormwater pollution prevention plan required under Part V of this permit must be modified within 14 calendar days of knowledge of the release to: provide a description of the release, the circumstances leading to the release, and the date of the release. In addition, the plan must be reviewed to identify measures to prevent the reoccurrence of such releases and to respond to such releases, and the plan must be modified where appropriate.

2. This permit does not authorize the discharge of hazardous substances or oil resulting from an on-site spill.

Developer

A. Notify Fuxan Engineering, Inc. of your intent to commence construction.

B. Sign a Certification of Storm Water Pollution Prevention Plan and return to Fuxan Engineering, Inc.

PRE-DEVELOPED SITE INFORMATION:

1. Total site acreage: 16.07
2. Land use: COMMERCIAL
3. Vegetation: BAHIA GRASS AND OAK TREES
4. Receiving waters or municipal separate storm water system: TROUT CREEK
5. 2 Year/24 Hour rainfall depth: 4.3"
6. Soil types: _____
7. Endangered species: NONE

PROJECT INFORMATION:

1. Project type: COMMERCIAL
2. Anticipated construction sequence is as follows:
   1. Complete erosion control installation
   2. Clearing and grubbing
   3. Earthwork activities
   4. Storm water system construction
   5. Utility construction
   6. Base and pavement construction
   7. Final stabilization

The BMP's listed in Part D of the Contractor section of the SWPPP shall be considered during all phases of construction.

3. Anticipated start date: JULY 2025
4. Anticipated completion date: DECEMBER 2026
5. Total acres disturbed: 15.0
6. Pre-developed "C" factor: 0.20
7. Post-developed "C" factor: 0.70
8. The storm water management system, upon completion of construction and appropriate certification and as-built submittals will be operated and maintained by SJC Ventures
9. The potential source of pollution from this project is on-site development and construction activity.

OWNER'S INSTRUCTIONS FOR MAINTENANCE AND INSPECTION OF STORMWATER FACILITIES

The entire stormwater system should be inspected on at least a semi-annual basis. This should include a visual inspection of the pond, pond banks, bleed-down orifices, other control structures, and discharge pipes. These should be kept free of debris and cleaned on a frequency as required to keep them functional, as designed. Mowing/clearing around the structures may be required to prevent vegetation from clogging them.

Wetland plants, if intentionally installed, should be monitored and maintained as required on the approved construction plans. Areas of littoral shelving, which are required to be vegetated but not intentionally planted, should not be cleared of the wetland plants. These areas should have as high a plant coverage as possible, for maximum water filtration.

Sediment sumps, if designed and installed, should have sediment removed as necessary to allow them to efficiently remove suspended particles. They should be re-dug to the original design specifications, if silted in.

For drainage vaults, the owner of the facility shall inspect the pond bottom periodically after heavy rainfall events to check for persistent ponding or pooling of water. All large debris shall be removed and disposed of elsewhere. If prolonged ponding persists, i.e., in excess of 72 hours, the owner shall rake or scarify the surface. If required, the soil in the area of ponding shall be removed and replaced with clean sandy, non-cohesive soils.

Please check the construction plans to see if written reports on monitoring or plant survival rates are required to be sent to any reviewing agencies. Written notes should always be kept which describe maintenance activities undertaken during each inspection.

Specific conditions of all permits may require additional maintenance activities above and beyond those outlined above. Please be aware of all permit conditions as issued by regulatory agencies to ensure permit compliance.

GENERAL EROSION AND TURBIDITY CONTROL NOTES

1. The Site Subcontractor shall be responsible for installation and maintenance of all erosion and turbidity controls and the quality and quantity of offsite or wetland discharges.
2. Prior to construction, the Site Subcontractor is responsible for having his dewatering plan and turbidity control plan approved by the applicable reviewing agencies. Refer to the project's permit approvals and permit conditions for agencies requiring such review and approval. Questions concerning appropriate techniques should be addressed to those agencies and/or discussed with the project engineer and owner.
3. The appropriate turbidity and erosion control methodologies selected by the Site Subcontractor for this project should be made following assessment of the plans and project site specific factors and after consultations as needed with the project engineer and appropriate agencies. The Site Subcontractor will be responsible for obtaining any and all necessary permits for such activity; several factors to consider are listed below:
   A. Clay content in excavated materials and/or permeabilities rates
   B. Depth of cut in ponds, trenches, or utility lines
   C. Ambient ground water levels
   D. Actual rainfall amounts and time of year relative to normal rainy season
   E. Proximity to wetlands, water bodies or offsite properties
   F. 'Class' designation of receiving water bodies (i.e., Outstanding Florida Waters, shellfish harvesting areas, etc.)
   G. Density, type, and proximity of upland vegetation to be retained during construction (for use as possible filtration areas)
   H. Fill height relative to natural grade and length and steepness of the proposed slopes
   I. Existing topography and directions of surface flow
   J. Type of equipment used
   K. Project type
   L. Duration of construction activities
   M. Separation distance of onsite ponds
   N. Ambient quality of surface and groundwater
   O. Temporary stockpile locations and heights
4. At the onset of construction, the Site Subcontractor, as the party responsible for implementation of the erosion and sediment control plan, shall assess the above described conditions and factors with respect to relative cost effectiveness and select the appropriate methods of protection. A fairly extensive list of techniques are presented below but it must be stressed that any or all of the following may be necessary to maintain water quality and quantity standards. The construction sequencing should be thought out in advance of initiation to provide adequate protection of water quality.
5. Discharges which exceed 29 N.T.U.'s over the background levels are in violation of state water quality standards. Discharges of water quantities which affect offsite properties or may damage wetlands are also prohibited by regulating agencies.
6. The erosion and turbidity control measures shown hereon are the minimum required for agency approval. Additional control and measures may be required due to the Site Subcontractor's construction sequence & unforeseen weather conditions. Any additional measures deemed necessary by the Site Subcontractor shall be included in the lump sum bid with no extras for materials and labor allowed.
7. Hay bales or silt screens shall be installed prior to land clearing to protect water quality and to identify areas to be protected from clearing activities and maintained for the duration of the project until all soil is stabilized.
8. Floating turbidity barriers shall be in place in flowing systems or in open water lake edges prior to initiation of earthwork and maintained for the duration of the project until all soil is stabilized.
9. No clay material shall be left exposed in any stormwater storage facility. If clay or sandy-clays are encountered during stormwater storage excavation, the Site Subcontractor shall notify the Engineer immediately before proceeding with further excavation. If the Engineer of Record has determined that such soils are non-cohesive and must be excavated to meet permit and design conditions, excavation may proceed after obtaining written authorization from the appropriate governing agency. If said soils are left exposed at the permitted and designed depth, the Site Subcontractor shall over-excavate the pond's bottom and side slopes by a minimum of twelve (12") inches and backfill with clean sands to help prevent suspension of fine particles in the water column.
10. The installation of temporary erosion control features shall be coordinated with the construction of the permanent erosion control features to the extent necessary to assure effective and continuous control of erosion and water pollution throughout the life of the construction phase.
11. The type of erosion control barriers used shall be governed by the nature of the construction operation and soil type that will be exposed. Silty and clayey material may require solid sediment barriers to prevent turbid water discharge, while sandy material may need only silt screens or hay bales to prevent erosion. Floating turbidity curtains should generally be used in open water situations. Diversion ditches or swales may be required to prevent turbid stormwater runoff from being discharged to wetlands or other water bodies. It may be necessary to employ a combination of barriers, ditches, and other erosion/turbidity control measures if conditions warrant.
12. Where pumps are to be used to remove turbid waters from construction areas, the water shall be treated prior to discharge to the wetlands. Treatment methods include, for example, turbid water being pumped into grassed swales or appropriate upland vegetated areas (other than upland preservation areas and wetland buffers), sediment basins, or confined by an appropriate enclosure such as turbidity barriers or low berms, and kept confined until turbidity levels meet State Water Quality Standards.
13. The Permittee shall schedule his operations such that the area of unprotected erodible earth exposed at any one time is not larger than the minimum area necessary for efficient construction operation, and the duration of exposed, uncompleted construction to the elements shall be as short as practicable. Clearing and grubbing shall be so scheduled and performed such that grading operations can follow immediately thereafter. Grading operations shall be so scheduled and performed that permanent erosion control features can follow immediately thereafter if conditions on the project permit.
14. Water derived from various dewatering methods should be passed through sufficiently vast areas of existing upland vegetation to filter out excess turbidity. If this is not sufficient, the water shall be retained in previously constructed permanent stormwater ponds or else retained in temporary sedimentation basins until the clarity is suitable to allow for its discharge. Plugging the outfalls from completed stormwater ponds may be needed to avoid discharge. However, such situations should be monitored closely in the event failure if water levels rise too high.
15. Water can be transported around the site by the use of internal swales or by pumps and pipes.
16. Sheet flow of newly filled or scraped areas may be controlled or contained by the use of brush barriers, diversion swales, interceptor ditches or low berms. Flow should be directed toward areas where sediments can sufficiently settle out.
17. Exposed soils shall be stabilized as soon as possible, especially slopes leading to wetlands. Stabilization methods include solid sod, seeding and mulching or hydromulching to provide a temporary or permanent grass cover mulch blankets, filter fabrics, etc., can be employed to provide vegetative cover.
18. Energy dissipaters (such as rip rap, a gravel bed, hay bales, etc.) shall be installed at the discharge point of pipes or swales if scouring is observed.
19. Attempt to install roadway curb and gutters as soon as possible to reduce the surface area for erosion to occur.
20. Implement storm drain inlet protection (hay bales or gravel) to limit sedimentation within the stormwater system. Perform inspections and periodic cleaning of sediments which wash out into the streets until all soil is stabilized.
21. Water discharge velocities from impounded areas and temporary sedimentation basins shall be restricted to avoid scouring in receiving areas.
22. If water clarity does not reduce to state standards rapidly enough in holding ponds, it may be possible to use chemical agents such as alum to flocculate or coagulate the sediment particles.
23. Hay bales, silt screens, or gravel beds can be added around the pipe or swale discharge points to help clarify discharges. Spreader swales may help dissipate cloudy water prior to contact with wetlands.
24. All fuel storage areas or other hazardous storage areas shall conform to accepted state or federal criteria for such containment areas.
25. Vehicle or equipment washdown areas will be sufficiently removed from wetlands or offsite areas.
26. Fugitive dust controls (primarily by using water spray trucks) shall be employed as needed to control windborn emissions.
27. If the above controls remain ineffective in precluding release of turbid water, especially during pond or utility line dewatering, then the contractor may be compelled to use a vertical dewatering system such as well points or sock drains to withdraw groundwater which may already be clear enough to allow for direct discharge to wetlands.
28. Ongoing inspections and periodic maintenance by the Site Subcontractor shall occur throughout construction as necessary to insure the above methods are working suitably. This may be needed daily, if conditions so warrant. Site Subcontractors are encouraged to obtain and thoroughly review The Florida Development Manual: a Guide to Sound Land and Water Management, which was developed by the State of Florida Department of Environmental Protection in 1988. This provides fairly in-depth discussions of recommended techniques and also provides specific design and technical standards. A copy of this document is available for review at Fuxan Engineering, Inc.
29. The contractor will perform daily inspections of all on-site wetlands within the construction area to ensure that water levels within those wetlands are not excessively impounded prior to the time when the permitted control structure or outfall is built. Water levels significantly above normal should be corrected at a frequency that prevents a change in the vegetative character or health of any wetlands.

PASCO COUNTY STANDARD SITE PLAN NOTES:

1. Owner/Developer: SJC Ventures, 1115 Howell Mill Rd., Suite 777, Atlanta, GA 30318
2. Engineer/Surveyor: Fuxan Engineering, Inc., 15018 Maurine Cove Ln., Odessa, Florida 33556, (813) 244-6194
3. Existing zoning: MPUD
4. Existing Land Use Classification: RES-3
5. Water service to be provided by Pasco County.
6. Sewage disposal service to be provided by Pasco County.
7. Electrical power to be provided by TECO.
8. Telephone service to be provided by Frontier.
9. Fire protection to be provided by the existing Fire Rescue adjacent to site.
10. The current site is vacant. Existing upland vegetation consists of Bahia grass and Oak trees.
11. Contours shown are based on North American Vertical Datum 1988 (NAVD 88).
12. All roadway standards to comply with the Manual of Uniform Minimum Standards, State of Florida.
13. All utility lines shall be installed underground and designed/ approved by the respective utilities.
14. Project lies Flood Zones "AE" & "X", according to Flood Insurance Rate Map, Map No. 12101C0436F for Pasco County, Community No. 120230, Pasco County, Florida, dated September 26, 2014
15. Sidewalks shall be five (5) feet wide, 4½" thick concrete, and 3000 p.s.i.
16. All easements to be a minimum of five (5) feet in width.
17. Medians and roadside clear zones shall be sodded or seeded & mulched.
18. All landscape and sodded areas along collector roads will be irrigated.
19. If during construction activities any evidence of historic resources, including but not limited to aboriginal or historic pottery, prehistoric stone tools, bone or shell tools, historic trash pits, or historic building foundation, are discovered, work shall come to an immediate stop and the Florida Department of Historic Resources (State Historic Preservation Officer) and Pasco County shall be notified within two working days of the resources found on the site.
20. SJC Ventures shall inspect and maintain the water detention system on a regular basis.
21. All sodded slopes over 4 to 1, shall be installed with sod pegs.
22. All demolition debris shall be removed from the site and legally disposed of.
23. The buildings shall have the finish floor elevation a minimum of 1' above the base flood elevation or as required by the Land Development Code.
24. Street lighting shall be provided per state and county regulations.
25. Fugitive dust shall be controlled by water trucks.
26. Onsite burning shall require fire marshal's approval.
27. The project drains into a proposed vault which drains to Trout Creek.
28. Maximum building height per LDC is 45 feet. Proposed building height is 15 feet 1 story.
29. Project will be completed in one phase.
30. Installation of fuel storage tanks requires review and approval by the Fire Marshal and the issuance of a separate building permit. Approval of the site plan does not constitute approval of the location of the fuel tanks.
31. All proposed signs must be applied for, approved, and permitted on an individual basis apart from any ultimately approved site plan. Approval of this site plan does not constitute approval of any signage.
32. Handicap parking spaces will be properly signed and striped in accordance with Florida Statute 316, the Manual on Uniform Traffic Control Devices, or other applicable standards.
33. The architect/engineer certifies that the site has been designed in accordance with the Americans with Disabilities Act.
34. All on-site parking spaces will be striped and signed in accordance with the Manual on Uniform Traffic Control Devices, latest edition. Parking spaces, directional arrows, and stop bars shall be striped in WHITE. It shall be the owner/developer's responsibility to properly sign and stripe in accordance with applicable standards.
35. All right-of-way work shall be a function of an approved Pasco Right-of-way Use Permit.
36. 20 feet by 20 feet clear site triangles shall be kept free of any signage plantings, trees, etc. in excess of three-and-a-half (3-1/2) feet in height.
37. No irrigation system or landscaping shall be installed in any County or State right-of-way without issuance of appropriate Right-of-Way Use Permit.
38. The owner/developer acknowledges that the site and its subsequent building permits shall comply with all rezoning/MPUD/PUD conditions.
39. Dumpster shall be used for refuse disposal.
40. Site triangle shall be unobstructed and shall be inspected and maintained in conformance with FDOT Index 546.
41. Sidewalk/multiuse path clear zone shall be free of obstacles, including but not limited to shrubs, trees, fences, above ground utilities i.e. power poles, street lights, guy anchors, fire hydrants, mail boxes, street signs and utility markers etc.
42. All the trees overhanging public Right Of Way/or trees within the ROW shall be trimmed and pruned to maintain a minimum vertical clear height of 8' from the finished ground surface of the sidewalk to the bottom of Canopy/ 16.0' clear height above the roadway paths.
43. If during construction activities any evidence of the presence of State or Federally protected plant and/or animal species is discovered, Pasco County and applicable agencies shall be notified within two working days of the plant and/or animal species found on the site. All work in the affected area shall come to an immediate stop until all pertinent permits have been obtained, agency written authorization to commence activities has been given, or unless compliance with state and federal guidelines can be demonstrated.
44. Fill will be delivered to the site, and no fill will be removed from the site.
45. Prior to the start of the clearing and grubbing, or any soil disturbance contact PC Stormwater Management at 727-834-3611 for a soil erosion and sediment control, pre-inspection meeting.
46. The soil erosion and sediment control devises shall be installed prior to construction, maintained throughout construction and until the site is permanently stabilized. (LDC 902.2)
47. All structures, including buffer walls, retaining walls, signage, etc. require building permits.
48. All demolition debris shall be removed from the site and legally disposed of.
49. Any off site disturbance shall be restored to pre or better condition.
50. As applicable, the owner/developer will provide copies of the required permits from the respective governing agencies, prior to issuance of the SDP.
51. Geotechnical notes:
   A. Should any noticeable soil slumping or sinkhole formation become evident, the applicant/developer shall immediately notify the County, Tampa Bay Water (TBW), and SWFWMD, and adopt one or more of the following procedures as determined to be appropriate by the County and SWFWMD.
      1. If the slumping or sinkhole formation becomes evident before or during construction activites, stop all work (except for mitigation activities) in the affected area and remain stopped until the County and SWFWMD approve resuming construction activities.
      2. Take immediate measures to ensure no surface water drains into the affected areas.
      3. Visually inspect the affected area.
      4. Excavate and backfill or grout as required to fill the affected area and prevent further subsidence.
      5. Use soil reinforcement materials in the backfill operation, when appropriate.
      6. If the affected area is in the vicinity of a water-retention area, maintain a minimum distance of two feet from the bottom of the retention area to surface of the lime-rock or karst connection.
      7. If the affected area is in the vicinity of a water-retention area and the above methods do not stabilize the collapse, relocate the retention area.
   B. Discharge of storm-water into depressions with direct or demonstrated hydrologic connection to the Floridan Aquifer shall be prohibited.
   C. The site shall be graded to within 12 inches for the final grade and prepared in accordance with the geotechnical/geological engineering report. Where fill is proposed it shall be placed in compliance with the geotechnical/geological engineering report recommendations (including any lift depths recommended) and compacted to a minimum density of 95% of the modified Proctor maximum dry density. Density tests to confirm compaction shall be required with the building pad area, before the next lift is placed. Foundation subgrade shall be prepared in accordance with the geotechnical/geological engineering report. Upon completion of the land development construction, a professional engineer shall provide a certification to Pasco County that the project, including each pad area, complies with the recommendations of the geotechnical/geological engineering report.
52. The contractor must provide a dewatering plan, if applicable, to Pasco County Engineering Inspections Department at (727) 834-3670, for review prior to the erosion control measures pre-inspection meeting.
53. If a project site contains an easement, especially a power company easement, a Letter of No Objection is required from the easement holder. By signing and sealing this plan the engineer of record is attesting that he/she has identified and accurately shown all easements of record on the plans.

SPECIFICATIONS FOR DESIGN AND INSTALLATION OF TRAFFIC CONTROL DEVICES ON PRIVATE ROADS

1. All traffic control devices shall be installed in conformance with the Manual on Uniform Traffic Control Devices and the Florida Department of Transportation standards.
2. Street name signs shall be 9-inch on all road classifications. All signs shall have 6-inch series B letters. All street name signs on private roads shall be standard D3 street name signs with the colors reversed; white background with green letters and border. At intersections with county or state maintained roads; the county of state maintained road shall be green background with white letters and border.
3. Any traffic control device for a private roadway placed in a county or state Right-of-Way shall be installed on the appropriate breakaway post assembly.
4. All parking spaces shall be striped in white.

PASCO COUNTY DEVELOPMENT REVIEW – STANDARD SITE PLAN NOTES

1. All utility construction shall comply with the Pasco County Standards for Design and Construction of Water and Wastewater Facilities Specifications, latest edition.
2. All on-site water and sewer facilities shall be owned and maintained by the owner/ developer.
3. Installation of fuel storage tanks requires review and approval by the Fire Marshal and the issuance of a separate building permit. Approval of the site plan does not constitute approval of the location of the fuel tanks.
4. All proposed signs must be applied for, approved, and permitted on an individual basis apart from any ultimately approved site plan. Approval of this site plan does not constitute approval of any signage.
5. Handicap parking spaces will be properly signed and striped in accordance with Florida Statute 316, the Manual on Uniform Traffic Control Devices, or other applicable standards.
6. The architect/engineer certifies that the site has been designed in accordance with the Americans with Disabilities Act.
7. All on-site parking spaces will be striped and signed in accordance with the Manual on Uniform Traffic Control Devices, latest edition. Parking spaces, directional arrows, and stop bars shall be striped in WHITE. It shall be the owner/developer's responsibility to properly sign and stripe in accordance with applicable standards.
8. The owner/developer acknowledges that this approval does not include any work in the County right-of-way. All right-of-way work shall be a function of an approved Pasco Right-of-way Use Permit.
9. All clear-site areas shall be kept free of any signage plantings, trees, etc. in excess of three-and-a-half (3-1/2) feet in height.
10. No irrigation system or landscaping shall be installed in any County or State right-of-way without issuance of appropriate Right-of-Way Use Permit.
11. The owner/developer acknowledges that the site and its subsequent building permits shall comply with all rezoning/MPUD/PUD conditions.
12. All structures, including buffer walls, retaining walls, signage, etc. require building permits.
13. If a project site contains an easement, especially a power company easement, a Letter of No Objection is required from the easement holder. By signing and sealing this plan the engineer of record is attesting that he/she has identified and accurately shown all easements of record on the plans.

STREET & DRAINAGE CONSTRUCTION NOTES:

1. Prior to construction, the Contractor shall obtain from the Engineer or Owner a copy of all pertinent permits related to this project. It is the Contractor's responsibility to assure that all construction activities are in compliance with the conditions of all permits and approvals. Contractor is also responsible for having his dewatering plan approved by SWFWMD.
2. All construction, materials and workmanship are to be in accordance with Pasco County Land Development Code and DOT Specifications, latest editions.
3. Grass and mulch, or solid sod, all areas in existing rights-of-way disturbed by construction.
4. Contractor shall be responsible for obtaining any and all road crossing or utility permits.
5. The existing underground utility lines shown hereon were taken from documents furnished by others and not field verified, therefore, the Engineer cannot guarantee the accuracy of same nor that all are shown. The Contractor shall expose all underground utility lines in coordination with the Owners to his satisfaction and make adjustments to same in the event there are conflicts with new construction.
6. Contractor shall verify locations and depths of existing water and sewer lines prior to beginning construction.
7. The locations and elevation of all service lines are to be determined in the field by Owner and/or Contractor prior to construction of same.
8. Fire hydrant, gate valve and blow-off valve assemblies shall consist of all pipe, valves, tees, fittings, and any and all other appurtenances comprising a complete, working unit.
9. All fire hydrants shall be flow tested and color coded based on flow results.
10. All 4"-12" PVC water main pipe shall be C-900 DR 18, conforming to the requirements found in AWWA Standard, latest edition at the time of plan approval. 16" water main shall be C-905 DR 25 PVC. All service pipe less than 4" in diameter shall be PVC Pressure Pipe; Pressure Rate 200; DR 21 per ASTM Standard D-2241. Water mains smaller than 2" in diameter shall be Class 1120 or 1220 ; Schedule 80 and meet the requirements of ASTM D-1785.
11. All water mains and fittings installed under this project shall be color coded or marked in accordance with subparagraph 62-555.320(21)(b)3, Florida Administrative Codes, using blue as the predominant color.
12. All aspects of reclaimed water system must comply with Chapter 17-610, F.A.C., latest edition.
13. All 8" sanitary sewer pipe shall be constructed at a 0.40% minimum slope unless otherwise noted.
14. Force mains shall be constructed of C-900 DR 18 PVC pigmented green.
15. Adjusting manhole tops to match grade and slope of the finish paving shall be included in the respective contract unit price for manholes, payment of which will constitute full compensation for the construction and completion of the manhole, and no additional payment will be allowed or made for adjusting manhole tops.
16. Bends shall be installed in force main or water main to avoid unforeseen conflicts in existing or proposed structures.
17. The joint deflection method shall be used where practical in lieu of installing bends.
18. All valve box assemblies located within roadways or parking areas shall be protected from truck traffic by use of 6" thick reinforced concrete pads (see detail).
19. Off-road utility easements shall be "stabilized" for access by maintenance vehicles.
20. Stub-out lines on the water main, force main, and reclaimed main shall have restrained joints from the main line to the stub-out.
21. All PVC pressure pipe shall have a minimum 36" cover.
22. All water mains shall be deflected vertically where crossing storm sewer pipe to obtain a minimum vertical distance of 18 inches between the outside of the water main and the outside of the storm sewer. Joints shall be located such that the distance from the storm sewer and water main joint is as far as practical.
23. Water mains should be laid at least 10 feet horizontally from any existing or proposed storm sewer.
24. At no time should vertical clearance between force main or gravity sewer and water main be less than 18" at crossing of same.
25. At no time should horizontal clearance between force main or gravity sewer and water main be less than 10' when same are parallelling each other.
26. Sanitary sewers, force mains and storm sewers should cross under water mains. Sanitary sewers, force mains and storm sewers crossing water mains shall be constructed to provide a minimum vertical distance of 18 inches between the invert of the upper pipe and the crown of the lower pipe whenever possible.
27. When sanitary sewers, force mains and storm sewers must cross a water main with less than 18 inches vertical distance, both the sewer and the water main shall be constructed of ductile iron pipe (DIP) at the crossing. DIP is not required for storm sewers if it is not available in the size proposed.) Sufficient lengths of DIP must be used to provide a minimum separation of 10 feet between the two joints. A joint of DIP and the crossing within 20 feet of the crossing must be leak free and mechanically restrained. A minimum vertical clearance of 6 inches must be maintained at the crossing.
28. Where there is no alternative to sewer and reclaimed pipes crossing over a water main, the criteria for minimum separation of 18 inches between lines and 10 feet between joints shall be required.
29. All crossings shall be arranged so that the sewer and reclaimed pipes joints and the water main pipe joints are equidistant from the point of crossing (pipes centered on the crossing).
30. Where a new pipe conflicts with an existing pipe, the new pipe shall be constructed of DIP and the crossing shall be arranged to meet the requirements above.
31. A minimum 10-foot horizontal separation shall be maintained in parallel installations between any type of sewer (including drainage inlets) and water main whenever possible.
32. In cases where it is not possible to maintain a 10-foot horizontal separation between any type of parallel sewer and water main, or a 5-foot separation between reclaimed main and water main, the water main must be laid in a separate trench or on an undisturbed earth shelf located on one side of the sewer, reclaimed main, or force main at such an elevation that the bottom of the water main is at least 18 inches above the top of the sewer.
33. Where it is not possible to maintain a vertical distance of 18 inches or a horizontal distance of 10 feet in parallel installations, the water main shall be constructed of DIP and the sewer, reclaimed main or the force main shall be constructed of DIP (if available in the size proposed) with a minimum vertical distance of 6 inches. The water main should be above the sewer, reclaimed main, or force main. Joints on the water main shall be located as far apart as possible from joints on the sewer, reclaimed main, or force main (staggered joints).
34. All subsurface construction shall comply with the "Trench Safety Act." The Contractor shall insure that the method of trench protection and construction is in compliance with the Occupational Safety and Health Administration (OSHA) Regulations.
35. All utility construction shall comply with the Pasco County Standards for Design and Construction Water and Wastewater Facilities Specifications, latest edition.

WATER & SEWER CONSTRUCTION NOTES:

1. Prior to construction, the Contractor shall obtain from the Engineer or Owner a copy of all pertinent permits related to this project. It is the Contractor's responsibility to assure that all construction activities are in compliance with the conditions of all permits and approvals.
2. Grass and mulch, or solid sod, all areas in existing rights-of-way disturbed by construction.
3. Contractor is to coordinate all work within, but not limited to, Pasco County rights-of-way with utility companies in order to prevent damage to utility lines and the making of adjustments to same, if required.
4. Contractor shall be responsible for obtaining any and all road crossing or utility permits.
5. The existing underground utility lines shown hereon were taken from documents furnished by others and not field verified, therefore, the Engineer cannot guarantee the accuracy of same nor that all are shown. Contractor shall expose all underground utility lines in coordination with the Owners to his satisfaction and make adjustments to same in the event there are conflicts with new construction.
6. Contractor shall verify locations and depths of existing water and sewer lines prior to beginning construction.
7. The locations and elevation of all service lines are to be determined in the field by Owner and/or Contractor prior to construction of same.
8. Fire hydrant, gate valve and blow-off valve assemblies shall consist of all pipe, valves, tees, fittings, and any and all other appurtenances comprising a complete, working unit.
9. All fire hydrants shall be flow tested and color coded based on flow results.
10. All 4"-12" PVC water main pipe shall be C-900 DR 18, conforming to the requirements found in AWWA Standard, latest edition at the time of plan approval. 16" water main shall be C-905 DR 25 PVC. All service pipe less than 4" in diameter shall be PVC Pressure Pipe; Pressure Rate 200; DR 21 per ASTM Standard D-2241. Water mains smaller than 2" in diameter shall be Class 1120 or 1220 ; Schedule 80 and meet the requirements of ASTM D-1785.
11. All water mains and fittings installed under this project shall be color coded or marked in accordance with subparagraph 62-555.320(21)(b)3, Florida Administrative Codes, using blue as the predominant color.
12. All aspects of reclaimed water system must comply with Chapter 17-610, F.A.C., latest edition.
13. All 8" sanitary sewer pipe shall be constructed at a 0.40% minimum slope unless otherwise noted.
14. Force mains shall be constructed of C-900 DR 18 PVC pigmented green.
15. Adjusting manhole tops to match grade and slope of the finish paving shall be included in the respective contract unit price for manholes, payment of which will constitute full compensation for the construction and completion of the manhole, and no additional payment will be allowed or made for adjusting manhole tops.
16. Bends shall be installed in force main or water main to avoid unforeseen conflicts in existing or proposed structures.
17. The joint deflection method shall be used where practical in lieu of installing bends.
18. All valve box assemblies located within roadways or parking areas shall be protected from truck traffic by use of 6" thick reinforced concrete pads (see detail).
19. Off-road utility easements shall be "stabilized" for access by maintenance vehicles.
20. Stub-out lines on the water main, force main, and reclaimed main shall have restrained joints from the main line to the stub-out.
21. All PVC pressure pipe shall have a minimum 36" cover.
22. All water mains shall be deflected vertically where crossing storm sewer pipe to obtain a minimum vertical distance of 18 inches between the outside of the water main and the outside of the storm sewer. Joints shall be located such that the distance from the storm sewer and water main joint is as far as practical.
23. Water mains should be laid at least 10 feet horizontally from any existing or proposed storm sewer.
24. At no time should vertical clearance between force main or gravity sewer and water main be less than 18" at crossing of same.
25. At no time should horizontal clearance between force main or gravity sewer and water main be less than 10' when same are parallelling each other.
26. Sanitary sewers, force mains and storm sewers should cross under water mains. Sanitary sewers, force mains and storm sewers crossing water mains shall be constructed to provide a minimum vertical distance of 18 inches between the invert of the upper pipe and the crown of the lower pipe whenever possible.
27. When sanitary sewers, force mains and storm sewers must cross a water main with less than 18 inches vertical distance, both the sewer and the water main shall be constructed of ductile iron pipe (DIP) at the crossing. DIP is not required for storm sewers if it is not available in the size proposed.) Sufficient lengths of DIP must be used to provide a minimum separation of 10 feet between the two joints. A joint of DIP and the crossing within 20 feet of the crossing must be leak free and mechanically restrained. A minimum vertical clearance of 6 inches must be maintained at the crossing.
28. Where there is no alternative to sewer and reclaimed pipes crossing over a water main, the criteria for minimum separation of 18 inches between lines and 10 feet between joints shall be required.
29. All crossings shall be arranged so that the sewer and reclaimed pipes joints and the water main pipe joints are equidistant from the point of crossing (pipes centered on the crossing).
30. Where a new pipe conflicts with an existing pipe, the new pipe shall be constructed of DIP and the crossing shall be arranged to meet the requirements above.
31. A minimum 10-foot horizontal separation shall be maintained in parallel installations between any type of sewer (including drainage inlets) and water main whenever possible.
32. In cases where it is not possible to maintain a 10-foot horizontal separation between any type of parallel sewer and water main, or a 5-foot separation between reclaimed main and water main, the water main must be laid in a separate trench or on an undisturbed earth shelf located on one side of the sewer, reclaimed main, or force main at such an elevation that the bottom of the water main is at least 18 inches above the top of the sewer.
33. Where it is not possible to maintain a vertical distance of 18 inches or a horizontal distance of 10 feet in



LEGEND

- EXISTING TREE TO BE REMOVED
- STAKED EROSION CONTROL

TREE LEGEND

- LA ---- LAUREL OAK (DIAMOND OAK)
- RM ---- RED MAPLE
- LI ---- LIVE OAK
- QP ---- QUEEN PALM

NOTE: Trees by nature are irregular in size and shape. Every effort is made to accurately locate trees. The tree size is determined at diameter breast height (DBH). The tree location is the center of the tree. This location may be different if located from a different direction. All tree locations should be field checked if critical to design.

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY

REVISIONS

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
No. 33133
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

STATE OF FLORIDA
DAVID G. FUXAN
PROFESSIONAL ENGINEER
DATE:
DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

DEMOLITION PLAN

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE DEMO	SHEET 3 OF 21 SHEETS



BUILDING SUMMARY

BUILDING 100	35,518 sf
BUILDING 150	10,416 sf
BUILDING 200	16,017 sf
BUILDING 300	14,017 sf
BUILDING 400	84,500 sf
TOTAL	160,468 sf

FAR = 160,468 sf / 699,867 sf = 0.23

Building Height 45'

REQUIRED SETBACKS

25' Front
30' Side

PARKING CALCULATIONS

Required Parking
160,468 sf x 1 Parking/300= 534 Spaces

Provided Parking
855 Standard Spaces
8 Covered Spaces
20 HC Spaces
883 Total Spaces

Bicycle Parking
883 Spaces x .02 = 18 Spaces

PROJECT AREA TABULATION

Proposed Buildings	2.75 ac	0.17%
Proposed Pavement	9.00 ac	0.56%
Proposed Pool/Patio	1.30 ac	0.08%
Open/Green	3.02 ac	0.19%
Overall Boundary	16.07 ac (699,867 sf)	100%

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY

REVISIONS

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DATE:
DAVID G. FUXAN, P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

PRELIMINARY PLAN

MEADOW POINTE TRACT 2

JOB NO.	2025-MP2-01
DESIGN	FUXAN
DRAWN	MIDDLETON
DATE	2-9-2025
FILE	PSP
PREPARED FOR:	SJC Ventures

Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet



Section A-A @ HC Spaces

NTS



PLAN VIEW

STANDARD
SIDEWALK GRADING DETAIL

NTS



* WHEN USED ON HIGH SIDE OF ROADWAYS, THE CROSS SLOPE OF THE GUTTER SHALL MATCH THE CROSS SLOPE OF THE ADJACENT PAVEMENT. THE THICKNESS OF THE LIP SHALL BE 6", UNLESS OTHERWISE SHOWN.

DROP CURB

NTS



TYPE "F" CURB AND GUTTER

NTS

PAVEMENT CONSTRUCTION NOTES

1. Pavement wearing surface shall be asphaltic concrete of type and thickness shown in detail and shall meet current Department of Transportation Specifications.
2. Pavement base shall be soil-cement, as designated in plans, and shall be compacted to a minimum thickness as shown.
3. All Portland Cement Concrete shall have a minimum compressive strength of 3000 p.s.i.
4. Subbase for soil-cement base construction shall be in accordance with D.O.T. Standard Specifications, latest edition.
5. Subgrade shall be proof-rolled to grade, as directed by the Engineer and approved by the Engineer with suitable compaction equipment to achieve a density of ninety-eight (98%) percent Modified Proctor for a depth of twelve (12) inches prior to placing any borrow material for soil-cement base.
6. Soil-cement shall be with full blend borrow material using limerock, shell or other material as approved by the Engineer.
7. Soil-cement design shall be developed using sample of borrow material delivered to job site.
8. Mixing for soil-cement base shall be started only after review and approval by the Engineer.
9. Soil-cement shall be inspected and approved by the Engineer prior to any paving operation.
10. All curbs and gutters shall be placed on a foundation of Type "B" stabilized subgrade with a minimum LBR value of 40 (or a minimum FBV of 75) which has been compacted to a minimum density of ninety-eight (98) percent of the maximum density as determined by AASHTO T 180 for a minimum depth of six (6) inches.

ALTERNATIVE BASE MATERIAL CRUSHED CONCRETE

Crushed concrete road base material should meet the following conditions:

1. Should be of uniform quality, free of all organics, steel rebar, asphalt debris, and any other deleterious material.
2. Should have a minimum Limerock Bearing Ratio (LBR) of 150, tested at a 500 foot frequency.
3. Single course lifts should not exceed 6-inches (loose).
4. Should conform to the gradation chart for graded aggregate base, FDOT Section 204 (1991), tested at a 500 foot frequency.
5. Should be compacted to a minimum of 98% of AASHTO T-180, tested at a 500 foot frequency.
6. Subgrade shall be proof-rolled to grade, as directed by the Engineer and approved by the Engineer with suitable compaction equipment to achieve a density of ninety-eight (98%) percent Modified Proctor for a depth of twelve (12) inches prior to placing crushed concrete base.



ONSITE LIGHT DUTY
ASPHALT PAVEMENT SECTION

NTS



ARONWOOD BLVD. AND ONSITE LIGHT DUTY
ASPHALT PAVEMENT SECTION

NTS



David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY

REVISIONS

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

DATE:

PAVEMENT SECTIONS AND DETAILS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE RS	SHEET 5 OF 21 SHEETS

FEMA 100 YR = 54.50

WETLAND CONSERVATION AREA CATEGORY I
SH 48.67

SWFWMD MODEL DATA
100 YR DHW = 54.57
25 YR DHW = 53.54
2.33 YR DHW = 49.32

SWFWMD MODEL DATA
100 YR DHW = 54.60
25 YR DHW = 53.57
2.33 YR DHW = 50.30

EXISTING DETENTION POND
25 YR DHW = 51.22
DLW = 50.17
NW = 48.67

EXISTING DETENTION POND
25 YR DHW = 53.12
DLW = 52.12
NW = 51.47

MAJOR TENANT A
BUILDING 100
35,518 SF
FF 56.00
ONE STORY

SHOPS - BLDG. 150
10,416 SF
FF 56.00
ONE STORY

SHOPS - BLDG. 200
16,017 SF
FF EL 56.00
ONE STORY

SHOPS - BLDG. 300
14,017 SF
FF 56.00
ONE STORY

MAJOR TENANT B
BLDG 400
84,500 SF
FF 56.70
2-STORIES
45' MAX. HT.

BRUCE B. DOWNS BLVD.
(County Road 581)
200' Right-of-Way
Asphalt Pavement

ARONWOOD BLVD.
Right-of-Way Varies

PROPOSED 350' RIGHT TURN LANE

PROPOSED 665' LEFT TURN LANE

PROPOSED 370' LEFT TURN LANE

PROPOSED 350' LEFT TURN LANE

RETAINING WALL
REFER TO ARCHITECTURAL PLANS FOR DETAILS

GENERATOR WITH FUEL TANK
SLAB EL. 55.50

REFER TO SHEET 7 FOR EXISTING CONTROL STRUCTURE MODIFICATIONS

PROPOSED SUMP WITH RETAINING WALL
REFER TO ARCHITECTURAL PLANS FOR DETAILS
TOP OF WALL 52.50
SUMP EL. 48.00

Existing Endwall
Inv.=46.17'

Existing Control Structure
Skimmer Elev.=51.51'
Conc. Wall Top
Elev.=50.09'

EXISTING DOUBLE 48" RCP'S

Flood Zone "AE"

Flood Zone "X"

15' Utility Easement
PB. 30, Pgs. 78-82

HEAVY DUTY TRENCH DRAIN GRATE EL. 52.00

TRUCK DOCKS

TRASH COMPACTORS

DUMPSTERS

DUMPSTER W/ ENCLOSURE

CONNECT ROOF DRAINS TO 12"

HEAVY DUTY PAVEMENT

LIGHT DUTY PAVEMENT

Elev=49.72'
TOW 08-15-24

Elev=50.02'
TOW 08-20-24

HC SPACES FLUSH WITH SIDEWALK

16'X 8' JUNCTION BOX/ CONFLICT STRUCTURE

7' SIDEWALK

INV. 51.70

INV. 51.70 POOL DECK

POOL DECK

REFER TO ARCHITECTURAL PLANS FOR POOL DECK DRAINS

TYPE C VAULT INLET TOP (TYP.)

PROPOSED MONUMENT SIGN

EXISTING SIDEWALK TO REMAIN

EXISTING TYPE F CURB

PROPOSED PAVEMENT AND CURB

PROPOSED MEDIAN PAVEMENT

REPLACE INLET TOP WITH MANHOLE TOP EL 55.70

EXISTING LEFT TURN LANE

3' CONCRETE TRAFFIC SEPARATOR

50' TAPER

100' TAPER

FEMA 100 YR = 54.70

SCALE: 1" = 50'

LEGEND

- PROPOSED STORM PIPE AND DRAINAGE STRUCTURE
- EROSION CONTROL
- TREES TO REMAIN
- PROPOSED GRADE
- DIRECTION OF SLOPE
- DRAINAGE STRUCTURE NUMBER
- UNDER PAVEMENT STORAGE VAULT CONSISTING OF PIPES OR CHAMBERS 148,000 CF REQUIRED STORAGE FROM EL 48.67 TO EL 51.22 105,620 SF AVAILABLE AREA NO PERCOLATION REQUIRED

Flood Note:
The subject parcel lies in Flood Zones "AE" & "X", according to Flood Insurance Rate Map, Map No. 12101C0436F for Pasco County, Community No. 120230, Pasco County, Florida, dated September 26, 2014

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY

REVISIONS

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
No. 33133
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

STATE OF FLORIDA
DAVID G. FUXAN
No. 33133
PROFESSIONAL ENGINEER

DATE:
DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

GRADING AND DRAINAGE PLAN

JOB NO.	2025-MP2-01
DESIGN	FUXAN
DRAWN	MIDDLETON
DATE	2-9-2025
FILE	GDP

MEADOW POINTE TRACT 2

PREPARED FOR: SJC Ventures

Elevations based on North American Vertical Datum 1988 (NAVD 88)
Conversion from NAVD 88 to NGVD 29 = +0.82 Feet

SHEET 6 OF 21 SHEETS



SECTION "S-S"



SECTION "R-R"



PLAN VIEW

EXISTING CONTROL STRUCTURE MODIFICATIONS

N.T.S.

NOTE:

CONTRACTOR SHALL SUBMIT SHOP DRAWINGS TO ENGINEER FOR APPROVAL PRIOR TO CONSTRUCTING CONTROL STRUCTURES.

ELEVATION SHOWN ARE IN NAVD 88

DRAINAGE STRUCTURE DATA

STRUCTURE NO.	STRUCTURE TYPE & SIZE	STRUCTURE TOP ELEV.	LINE TYPE	LINE DIAM. INCHES	LINE LENGTH FEET	LINE SLOPE %	LINE INVERT ELEV. THIS STR.	LINE INVERT ELEV. NEXT STR.	LINE FALL IN FEET	STRUCTURE LOCATION & REMARKS
1	GRATE TOP INLET TYPE C	53.00	RCP	-	-	-	50.00	-	-	CONNECT TO STORM STORAGE VAULT
2	GRATE TOP INLET TYPE C	53.00	RCP	-	-	-	50.00	-	-	CONNECT TO STORM STORAGE VAULT
3	GRATE TOP INLET TYPE C	55.20	HDPE	12	118	-	50.50	50.00	0.50	
5										
4	GRATE TOP INLET TYPE C	55.20	HDPE	12	82	-	50.50	50.00	0.50	
5	GRATE TOP INLET TYPE C	55.30	HDPE	12	65	-	50.00	49.50	0.50	CONNECT TO STORM STORAGE VAULT
6	GRATE TOP INLET TYPE C	52.00	RCP	18	122	-	49.50	49.30	0.20	
7	GRATE TOP INLET TYPE C	52.00	RCP	18	92	-	49.30	49.10	0.20	
8	GRATE TOP INLET TYPE C	52.00	RCP	18	62	-	49.10	48.90	0.20	
9	GRATE TOP INLET TYPE C	52.00	RCP	18	40	-	48.90	48.90	-	CONNECT TO STORM STORAGE VAULT
10	GRATE TOP INLET TYPE E	54.70	RCP	24	90	-	51.40	51.20	0.20	
11	GRATE TOP INLET TYPE E	54.50	RCP	24x30	127	-	51.20	51.00	0.20	
12	GRATE TOP INLET TYPE E	54.30	RCP	30	90	-	51.00	50.90	0.10	CONNECT TO STORM STORAGE VAULT
13	GRATE TOP INLET TYPE C	54.90	RCP	15	122	-	49.60	49.30	0.30	
14	GRATE TOP INLET TYPE C	54.70	RCP	15	122	-	49.30	49.00	0.30	
15	GRATE TOP INLET TYPE C	54.50	RCP	18	92	-	49.00	49.00	-	CONNECT TO STORM STORAGE VAULT
16	GRATE TOP INLET TYPE C	53.50	RCP	15	40	-	49.00	48.90	0.10	CONNECT TO STORM STORAGE VAULT
17	GRATE TOP INLET TYPE C	54.00	RCP	18	200	-	51.00	50.50	0.50	
18	GRATE TOP INLET TYPE C	53.00	RCP	18	200	-	50.50	50.00	0.50	
19	GRATE TOP INLET TYPE C	52.50	RCP	18	105	-	50.00	49.90	0.10	
20	MITERED END SECTION	-	RCP	18	-	-	49.90	-	-	
YD1	YARD INLET	54.70	HDPE	8	235	-	52.70	52.30	0.40	
YD2	YARD INLET	55.50	HDPE	8	80	-	52.30	51.90	0.40	
TD3	YARD INLET	55.00	HDPE	8	75	-	51.90	51.90	-	CONNECT TO STORM STORAGE VAULT
TD4	YARD INLET	54.70	HDPE	8	117	-	52.70	52.30	0.40	
YD5	YARD INLET	55.20	HDPE	8	77	-	52.30	51.90	0.40	
YD6	YARD INLET	54.70	HDPE	8	70	-	51.90	51.90	-	CONNECT TO STORM STORAGE VAULT
BP-1	JUNCTION BOX 8'x 6'	54.70	ERCP	43"X 68"	415	-	(S) 49.09 (N) 47.23	46.57	0.66	
BP-3A										
BP-3	MANHOLE TYPE J	54.90	RCP	36	60	-	(E) 48.78 (W) 49.78	49.90	-0.12	BOTTOM EL 47.70
BP-3A	JUNCTION BOX & CONFLICT STRUCTURE	54.50	RCP	36	60	-	46.57	-	-	SEE DETAIL ON SHEET 16

NOTES
* ALL STORM SEWER SHALL BE RCP
* ALL STORM STRUCTURES INCLUDING GRATES SHALL BE HEAVY TRAFFIC RATED
* ALL DRAINAGE CULVERT JOINTS SHALL BE WRAPPED PER FDOT INDEX 280
* PAVE INVERTS IN DRAINAGE STRUCTURES TO PREVENT IMPOUNDED WATER

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY

REVISIONS

Engineering Business Certificate of Authorization No.: 26548
Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN LICENSED PROFESSIONAL ENGINEER No. 33133 STATE OF FLORIDA

DATE:

DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

STRUCTURE DATA & CONTROL STRUCTURE DETAILS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE STR	SHEET 7 OF 21 SHEETS



SECTION N1

- NO SCALE -



SECTION N2

- NO SCALE -



SECTION N3

- NO SCALE -



SECTION S1

- NO SCALE -



SECTION S2

- NO SCALE -



SECTION S3

- NO SCALE -

NOTE:
SOD ALL SLOPES 4:1 AND STEEPER.

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY

REVISIONS

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DATE:
DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

CROSS SECTIONS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE SEC	SHEET 8 OF 21 SHEETS



SECTION W1

- NO SCALE -



SECTION E1

- NO SCALE -



SECTION E2

- NO SCALE -



SECTION W2

- NO SCALE -



SECTION E3

- NO SCALE -



SECTION W3

- NO SCALE -

NOTE:
SOD ALL SLOPES 4:1
AND STEEPER.

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by
David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed,
and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY

REVISIONS

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
No. 33133
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

STATE OF FLORIDA PROFESSIONAL ENGINEER

DATE:
DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

CROSS SECTIONS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE SEC	SHEET 9 OF 21 SHEETS





SECTIONAL VIEW
NTS

NOTES:

1. THE DEVELOPER'S ENGINEER SHALL INVESTIGATE THE EXISTING PAVEMENT LAYER TYPES AND DEPTHS BY RESEARCHING "RECORD/AS-BUILT DRAWINGS" AND/OR PERFORM GEOTECHNICAL BORINGS.
2. THE NEW PAVEMENT SHALL PROVIDE THE MINIMUM STRUCTURAL NUMBER AS FOLLOWS: TYPE 2 – 2.34, TYPE 1 – 3.50, COLLECTOR 3.70, ARTERIAL 4.00.

NOTE:
NO DEVIATIONS TO THIS DETAIL WILL BE PERMITTED UNLESS APPROVED BY THE COUNTY ENGINEER. ANY PROPOSED ALTERATIONS SHALL BE CLEARLY IDENTIFIED AND HIGHLIGHTED ON DETAIL.

PASCO COUNTY ENGINEERING SERVICES	PAVEMENT TIE-IN SAW CUT DETAIL	Sheet No. 1 of 1
DESIGN STANDARDS	APPROVED BY JCW / BCC APPROVAL / REVISED	Index No. 101



TYPICAL WIDENING SECTION

MAINLINE WIDENING FOR RIGHT TURN AND LEFT TURN LANES

OPTIONAL BASE GROUP 15 (TYPE B - 12.5) (9") (ONLY) WITH TYPE SP STRUCTURAL COURSE (TRAFFIC LEVEL C) (3") AND FRICTION COURSE FC-5 (3/4") (RUBBER)

SHOULDER WIDENING

OPTIONAL BASE GROUP 01 (TYPE B - 12.5) (4") (ONLY) WITH TYPE SP STRUCTURAL COURSE (TRAFFIC LEVEL C) (1 1/2") AND FRICTION COURSE FC-5 (3/4") (RUBBER)

DRIVEWAY CONSTRUCTION FOR PARCEL 3

OPTIONAL BASE GROUP 15 (TYPE B - 12.5) (9") (ONLY) WITH TYPE SP STRUCTURAL COURSE (TRAFFIC LEVEL C) (3") AND FRICTION COURSE FC-5 (3/4") (RUBBER)

GENERAL NOTES:

A. ALL WORK PERFORMED WITHIN THE RIGHT-OF-WAY AND WORK LIMITS SHOWN IN THE PLANS SHALL CONFORM TO:
   1. FLORIDA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (2025), (aka: STANDARD SPECS.)
   2. FLORIDA DEPARTMENT OF TRANSPORTATION DESIGN STANDARDS FOR DESIGN, CONSTRUCTION , MAINTENANCE AND UTILITY OPERATIONS ON THE STATE HIGHWAY SYSTEM (JAN. 2025) (aka: STANDARD INDEX) .
   3. FLORIDA DEPARTMENT OF TRANSPORTATION ROADWAY PLANS PREPARATION MANUAL, VOLUME 1, CHAPTER 2. (JAN. 2025)
   4. FLORIDA DEPARTMENT OF TRANSPORTATION FLEXIBLE PAVEMENT DESIGN MANUAL FOR NEW CONSTRUCTION AND PAVEMENT REHABILITATION (JAN. 2025) .
   5. DESIGN STANDARDS FOR RESURFACING, RESTORATION AND REHABILITATION (R-R-R) OF STREETS AND HIGHWAYS, FLORIDA DEPARTMENT OF TRANSPORTATION ROADWAY PLANS PREPARATION MANUAL, VOLUME 1, CHAPTER 25 (JAN. 2025)
   6. MANUAL OF UNIFORM MINIMUM STANDARDS FOR DESIGN, CONSTRUCTION AND MAINTENANCE FOR STREETS AND HIGHWAYS (COMMONLY KNOWN AS THE "FLORIDA GREEENBOOK") JAN. 2025)
   7. FLORIDA DEPARTMENT OF TRANSPORTATION STRUCTURES STANDARD DRAWINGS RELEASE 2025.
B. THE APPLICANT MUST NOTIFY PASCO COUNTY 24 HOURS IN ADVANCE OF STARTING PROPOSED WORK.
C. ALL TRAFFIC STRIPES AND MARKINGS ARE TO BE LEAD-FREE , NON-SOLVENT BASED THERMOPLASTIC. THE PERMITTEE SHALL PROVIDE THE DEPARTMENT WITH MANUFACTURER'S CERTIFICATION PRIOR TO ISSUANCE OF "FINAL ACCEPTANCE".
D. LANE CLOSURES SHALL OCCUR BETWEEN 7:00 PM AND 6:00 AM UNLESS LANE CLOSURE CALCULATIONS ARE PROVIDED AND/OR APPROVAL IS GUARANTEED BY PASCO COUNTY.
E. PROTECT ROADSIDE SWALES FROM EROSION AND SILTATION DURING CONSTRUCTION.
F. SOD ALL DISTURBED AREAS.

LEGEND

- PROPOSED STORM PIPE AND DRAINAGE STRUCTURE
- EROSION CONTROL
- 2.5% PROPOSED GRADE
- DIRECTION OF SLOPE
- 20 DRAINAGE STRUCTURE NUMBER

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY
	REVISIONS	

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
No. 33133
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN STATE OF FLORIDA PROFESSIONAL ENGINEER

DATE:

DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

BRUCE B. DOWNS TURN LANES

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE RT01	SHEET 10 OF 21 SHEETS



NOTE: SOD ALL DISTURBED AREAS

SCALE: 1" = 5' VERTICAL
1" = 10' HORIZONTAL

DATE	DESCRIPTION	BY

REVISIONS

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by
David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed,
and the signature must be verified on any electronic copies.

DATE:

DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN LICENSE No. 33133 STATE OF FLORIDA PROFESSIONAL ENGINEER

BRUCE B. DOWNS SECTIONS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE RT02	SHEET 11 OF 21 SHEETS

STOP
R1-1
30" x 30"
W/ D3 STREET
NAME SIGN

RIGHT TURN ONLY
FTP-32-04
24"x 30"

WETLAND
CONSERVATION AREA
CATEGORY I
SH 48.67

GENERATOR WITH
FUEL TANK
SLAB EL 55.50

SWFWL

WSB25

25'

EXISTING
DETENTION POND
25 YR DHW = 51.22
DLW = 50.17
NW = 48.67

SUMP

DUMPSTER
W/ ENCLOSURE

45

46

47

48

49

50

15' Utility Easement
PB. 30, Pgs. 78-82

220' R/W

200'

100' TAPER

50' TAPER

TRUCK
DOCKS

TRASH
COMPACTORS

DUMPSTERS

MAJOR
TENANT A
BUILDING 100
35,518 SF
FF 56.00
ONE STORY

SHOPS - BLDG. 150
10,416 SF
FF 56.00
ONE STORY

24" WHITE STOP BAR
(ENSURE 4' SEPARATION
BETWEEN STOP BAR AND
CROSSING)

50'R

ADA RAMPS

HC SPACES FLUSH
WITH SIDEWALK

POOL DECK

MAJOR TENANT B
BLDG 400
84,500 SF
FF 56.70
2-STORIES
45' MAX. HT.

POOL DECK

POOL DECK

BISTRO
OUTDOOR SEATING

PROPOSED 5'
CONCRETE SIDEWALK

PROPOSED
MONUMENT SIGN

PROPOSED 350' RIGHT TURN LANE

PROPOSED 665' LEFT TURN LANE

BRUCE B. DOWNS BLVD.
(County Road 581)
200' Right-of-Way
Asphalt Pavement

36'

5'

12'

50' TAPER

PROPOSED
MONUMENT SIGN

SHOPS - BLDG. 200
16,017 SF
FF EL 56.00
ONE STORY

SHOPS - BLDG. 300
14,017 SF
FF 56.00
ONE STORY

PROPOSED
MONUMENT SIGN

PROPOSED 5'
CONCRETE SIDEWALK

EXISTING SIDEWALK
TO REMAIN

TRAFFIC

CWS

EXISTING
MONUMENT SIGN

ARONWOOD BLVD.
Right-of-Way Varies

PROPOSED 370' LEFT TURN LANE

50' TAPER

12'

24'

50' TAPER

PROPOSED 350' LEFT TURN LANE

EXISTING LEFT TURN LANE

PROPOSED MEDIAN PAVEMENT

24" WHITE STOP BAR
(ENSURE 4' SEPARATION
BETWEEN STOP BAR AND
CROSSING)

STOP
R1-1
30" x 30"
W/ D3 STREET
NAME SIGN

60'



NOTES:

1. Foundation Notes for Slip Base:
   A. See FOUNDATION TABLE on Sheet 3 for foundation reinforcement details and dowel length.
2. Slip Base Fabrication Notes:
   A. The difference between the O.D. of the post and I.D. of the sleeve shall not be more than 1/4".
   B. The WELDED STUB BASE and lower STUB/SLEEVE BASE PLATE may be flame-cut using galvanized steel as an option to aluminum. The upper portion of the SLIP BASE must be aluminum.
   C. Either a Welded Stub Base or Bolted Stub/Sleeve Base may be used in Slip Base.
   D. For cast base plates bolted to foundation studs, use a Foundation stub the same size as the high column (Pole).
3. Slip-Base Assembly Instructions:
   A. Assemble the Slip Base as follows:
      1. Insert Post into Sleeve and connect using 2 - 1/2" diameter Sleeve Bolts.
      2. Assemble top base plate to bottom Base Plate using 4 - 1" diameter High Strength with 3 washers per bolt. (See Detail "A")
         a. Place one washer on each Base Bolt between the Bottom Base Plate and the Bolt Keeper Plate.
         b. Place the next washer between the Bottom Base Plate and the Bolt Keeper Plate.
         c. Use the remaining washers as shims to plumb the post.
         d. Add the top base plate section.
         e. Place one washer between the Top Base Plate and the Nut.
   B. Orient the Bolt Keeper Plates in the Direction of Traffic.
   C. Tighten Base Bolts as follows:
      1. Tighten Base Bolts to the maximum possible with a 12" to 15" wrench (this will tell the washers and shims are tight and in place).
      2. Loosen each Base Bolt one turn.
      3. Under the supervision of the Engineer, use a calibrated torque wrench to tighten Base Bolts to torque values in SLIP BASE DETAILS Table. Over-tightened Base Bolts are not permitted.
      4. Tack weld washers at the junction with nuts to prevent loosening. Repair damaged galvanizing.
   D. Obtain a tight sleeve connection by placing 4 galvanized steel shims between the column (post) and sleeve. Space the shims evenly around the perimeter of the column (1 between each bolt). Use only those shims that are 1" shorter than the height of the sleeve.

SLIP BASE DETAILS

Column (Post) Size										
Outside Dia.	Wall Thickness (t)	Base Plate Thickness (A)	Sleeve Length (Min.)	Sleeve Height "H"	Base Plate Width "W"	Base Plate Length "L"	Torque (ft-lbs)	Holes Size "D"	SHIM "S"	"R"
4"	¼"	4½"	9"	½"	8"	¾"	25	1¼"	1½"	1⅛"
4½"	¼"	4½"	9"	½"	8"	¾"	25	1¼"	1½"	1⅛"
5"	¼"	5½"	7"	½"	8"	¾"	25	1¼"	1½"	1⅛"
6"	¼"	6½"	9"	½"	8"	1"	25	1¼"	1½"	1⅛"
8"	¼"	8½"	12"	½"	11"	1"	25	1¼"	1½"	1⅛"

LAST REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	SINGLE COLUMN GROUND SIGNS	INDEX	SHEET
11/01/22				700-010	4 of 11

SLIP BASE AND FOUNDATION DETAILS

100 50 0 50 100

SCALE: 1" = 50'

LEGEND

30' CLEAR SIGHT TRIANGLE PER PASCO CO. NOTHING ABOVE 2' IN HEIGHT FROM THE PAVEMENT ELEVATION (EXCEPT FOR THE STOP POST) SHOULD BE PLACED IN THESE SITE TRIANGLES

ALL STRIPING SHALL BE THERMOPLASTIC.
ALL SIGNS SHALL BE DECORATIVE.

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY
	REVISIONS	

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
No. 33133
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194
STATE OF FLORIDA PROFESSIONAL ENGINEER
DAVID G. FUXAN

DATE:
DAVID G. FUXAN, P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

SIDEWALK, SIGNING, & PAVEMENT MARKING PLAN

JOB NO.	MEADOW POINTE TRACT 2
2025-MP2-01	
DESIGN: FUXAN	
DRAWN: MIDDLETON	PREPARED FOR: SJC Ventures
DATE: 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE: SPM	SHEET 12 OF 21 SHEETS

GENERAL NOTES:

1. Cross Slopes and Grades:
   - A. Sidewalk, ramp, and landing slopes (i.e. 0.02, 0.05, and 1:12) shown in this Index are maximums. With approval of the Engineer, provide the minimum feasible slope where the requirements cannot be met.
   - B. Landings must have cross-slopes less than or equal to 0.02 in any direction.
   - C. Maintain a single longitudinal slope along each side of the curb ramp. Ramp slopes are not required to exceed 15 feet in length.
   - D. Joints permitted at the location of Slope Breaks. Otherwise locate joints in accordance with Index 522-001. No joints are permitted within the ramp portion of the Curb Ramp.
2. Curb, Curb and Gutter and/or Sidewalk:
   - A. Refer to Index 522-001 for concrete thickness and sidewalk details.
   - B. Remove any existing curb, curb and gutter, or sidewalk to the nearest joint beyond the curb transition or to the extent that no remaining section is less than 5 feet long.
   - C. Width of Curb Ramp is 4'-0" minimum. Match sidewalk or Shared Use Path width as shown in the Plans.
3. Curb Ramp Alpha-Identification:
   - A. Sidewalk curb ramp alpha-identifications (e.g. CR-A) are provided for reference purposes in the Plans.
   - B. Alpha-identifications CR-I and CR-J are intentionally omitted.
4. Detectable Warnings:
   - A. Install detectable warnings in accordance with Specification 527.
   - B. Place detectable warnings across the full width of the ramp or landing, to a minimum depth of 2 feet measured perpendicular to the curb line and no greater than 5 feet from the back of the curb or edge of pavement.
   - C. If detectable warnings are shown in the Plans on slopes greater than 5%, align the truncated domes with the centerline of the ramp; otherwise, the truncated domes are not required to be aligned.



CURB RAMP NOMENCLATURE

LAST REVISION 11/01/21	REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	DETECTABLE WARNINGS AND SIDEWALK CURB RAMPS	INDEX 522-002	SHEET 1 of 7



ISOMETRIC VIEW



ISOMETRIC VIEW



PLAN VIEW

NOTE: For Example of CR-A used in Radial Curb Returns, See Sheet 7.

CR-A



PLAN VIEW

CR-B



SECTION A-A

SIDEWALK CURB RAMPS CR-A AND CR-B

LAST REVISION 11/01/20	REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	DETECTABLE WARNINGS AND SIDEWALK CURB RAMPS	INDEX 522-002	SHEET 2 of 7



PLAN VIEW

CR-C



CONSTRUCTION OF SIDEWALK CURB IN CUT SECTIONS



NOTE: For additional information on sidewalk curb construction, see SIDEWALK CURB OPTIONS details.

SECTION B-B



SIDEWALK CURB OPTIONS

SIDEWALK CURB RAMPS CR-C AND SIDEWALK CURB

LAST REVISION 11/01/20	REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	DETECTABLE WARNINGS AND SIDEWALK CURB RAMPS	INDEX 522-002	SHEET 3 of 7



ISOMETRIC VIEW



OPTION A



OPTION B

ISOMETRIC VIEW



OPTION A



OPTION B

ISOMETRIC VIEW



OPTION A



OPTION B

ISOMETRIC VIEW



PLAN VIEW

CR-D



PLAN VIEW

CR-E



PLAN VIEW

CR-F

PLAN VIEW

CR-G

SIDEWALK CURB RAMPS CR-D, CR-E, CR-F & CR-G

LAST REVISION 11/01/21	REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	DETECTABLE WARNINGS AND SIDEWALK CURB RAMPS	INDEX 522-002	SHEET 4 of 7



ISOMETRIC VIEW



ISOMETRIC VIEW



OPTION A



OPTION B

ISOMETRIC VIEW

PLAN VIEW

CR-H

PLAN VIEW

CR-K

PLAN VIEW

CR-L

SECTION C-C

SECTION D-D

NOTES:
1. Crosswalk Width and Configuration Vary; Must Conform to Index 711-001.
2. 15' Radius Curve Shown for CR-L.
3. For additional information on sidewalk curb construction, see SIDEWALK CURB OPTIONS details, on Sheet 3.

SIDEWALK CURB RAMPS CR-H, CR-K & CR-L

LAST REVISION 11/01/20	REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	DETECTABLE WARNINGS AND SIDEWALK CURB RAMPS	INDEX 522-002	SHEET 5 of 7







LANDINGS FOR CURB RAMPS WITHOUT SIDEWALKS
(See CR-F, CR-G & CR-K Respectively For Detectable Warning Details/Options)



ISOMETRIC VIEW
(CR-C Shown, Other Similar)



NOTE: Remove Elevated Pavement By Spading And Rolling, Smooth Milling, or Grinding.

SECTION E-E

PAVEMENT RELIEF DETAILS



OPTION A



OPTION B

DETECTABLE WARNING ON FLUSH SHOULDER SIDEWALKS

CURB RAMPS WITHOUT SIDEWALKS AND FLUSH SHOULDER SIDEWALKS

LAST REVISION 11/01/20	REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	DETECTABLE WARNINGS AND SIDEWALK CURB RAMPS	INDEX 522-002	SHEET 6 of 7

NOTES:
1. Where crosswalk markings are used, ramps must fall within the crosswalk limits. A clear space of 48" minimum is required at the bottom of the ramp within a marked crosswalk. If crosswalk markings are not present, a clear space of 48" minimum is required at the bottom of the ramp outside of active travel lanes.
2. Crosswalk widths and configurations vary; must conform to Index 711-001.
3. Flangeway Gap may be up to 3" for Freight-only Railways.



RAILROAD CROSSING



CURB RAMPS WITHIN RADIAL RETURN



CURB RAMPS OUTSIDE RADIAL RETURN



LINEAR SIDEWALK RAMPS

PLACEMENT OF SIDEWALK CURB RAMPS AT CURBED RETURNS (TYP.)

RAILROAD CROSSING AND CURB RAMPS AT CURBED RETURNS

LAST REVISION 11/01/20	REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	DETECTABLE WARNINGS AND SIDEWALK CURB RAMPS	INDEX 522-002	SHEET 7 of 7

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY
	REVISIONS	

Engineering Business Certificate of Authorization No.: 26548
Fuxan Engineering, Inc.
No. 33133
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN — STATE OF FLORIDA — PROFESSIONAL ENGINEER

DATE:
DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

SIDEWALK DETAILS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE SWD	SHEET 13 OF 21 SHEETS

INTERSECTION SIGHT DISTANCE: 4-LANE UNDIVIDED



4-LANE UNDIVIDED

Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)
≤ 25	295	210	100
30	355	255	120
35	415	295	135
40	475	335	155
45	530	375	175
50	590	420	195
55	650	460	215
60	705	500	230
65	765	545	250
70	825	585	270

Passenger Vehicle

Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)
≤ 25	375	265	125
30	450	320	150
35	525	375	175
40	600	425	200
45	675	480	220
50	750	530	245
55	825	585	270
60	900	640	295
65	975	690	320
70	1050	745	345

SU Vehicle

Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)
≤ 25	450	320	150
30	540	385	180
35	630	450	205
40	720	510	235
45	810	575	265
50	900	640	295
55	990	700	325
60	1080	765	355
65	1170	830	385
70	1255	890	410

Combination Vehicle

SIGHT DISTANCE (d) AND RELATED DISTANCES (d_L, d_r) (FEET)
4 LANE UNDIVIDED

Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)
≤ 25	315	175	90
30	375	205	110
35	440	245	130
40	500	275	145
45	565	310	165
50	625	345	180
55	690	380	200
60	750	410	215
65	815	450	235
70	875	480	255

Passenger Vehicle

Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)
≤ 25	400	220	115
30	480	265	140
35	560	310	165
40	640	350	185
45	720	395	210
50	800	440	230
55	880	485	255
60	960	525	280
65	1040	570	300
70	1120	615	325

SU Vehicle

Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)
≤ 25	475	260	140
30	570	315	165
35	665	365	195
40	760	420	220
45	855	470	245
50	950	520	275
55	1045	575	300
60	1140	625	330
65	1235	675	355
70	1330	730	385

Combination Vehicle

SIGHT DISTANCE (d) AND RELATED DISTANCES (d_L, d_r) (FEET)
4-LANE UNDIVIDED WITH LEFT TURN LANE



4-LANE UNDIVIDED WITH LEFT TURN LANE



4-LANE UNDIVIDED WITH LEFT TURN LANE AND OPTIONAL LANE

Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)
≤ 25	315	225	70
30	375	265	80
35	440	315	95
40	500	355	110
45	565	400	120
50	625	445	135
55	690	490	150
60	750	530	160
65	815	580	175
70	875	620	190

Passenger Vehicle

Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)
≤ 25	405	290	90
30	480	340	105
35	560	400	120
40	640	455	135
45	720	510	155
50	800	570	170
55	880	625	190
60	960	680	205
65	1040	740	220
70	1125	800	240

SU Vehicle

Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)
≤ 25	475	340	105
30	570	405	125
35	665	470	145
40	760	540	165
45	855	605	185
50	950	675	205
55	1045	740	225
60	1140	810	245
65	1235	875	265
70	1330	945	285

Combination Vehicle

SIGHT DISTANCE (d) AND RELATED DISTANCES (d_L, d_r) (FEET)
4-LANE UNDIVIDED WITH LEFT TURN LANE AND OPTIONAL LANE

NOT TO SCALE

LEGEND

Areas Free Of Sight Obstructions

NOTE:
1. See Figure 212.11.1 for origin of clear sight line on the minor road.

EXHIBIT 212-5
01/01/2025

INTERSECTION SIGHT DISTANCE: 6-LANE DIVIDED



6-LANE DIVIDED

Median 22' or Less				
Design Speed (mph)	d_x (Ft.)	d_L (Ft.)	d_r (Ft.)	d_m (Ft.)
≤ 25	350	250	65	300
30	415	295	80	355
35	485	345	90	415
40	555	395	105	470
45	625	445	115	530
50	690	490	130	585
55	760	540	140	645
60	830	590	155	705
65	900	640	170	765
70	970	690	180	825

Passenger Vehicle

25'-64' MEDIAN				
Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)	d_{rL} (Ft.)
≤ 25	315	225	275	200
30	375	265	330	240
35	440	315	385	280
40	500	355	445	320
45	565	400	500	360
50	625	445	555	400
55	690	490	610	440
60	750	530	665	480
65	815	580	720	520
70	875	620	775	560

Median 35' or Less				
Design Speed (mph)	d (d_x) (Ft.)	d_L (Ft.)	d_r (Ft.)	d_m (Ft.)
≤ 25	473	340	75	415
30	570	405	90	495
35	665	470	105	580
40	760	540	120	660
45	855	605	135	745
50	955	675	155	830
55	1050	745	170	915
60	1145	810	185	995
65	1240	880	200	1080
70	1330	940	210	1155

SU Vehicle

40'-64' Median					
Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)	d_v (Ft.)	d_{rL} (Ft.)
≤ 25	400	285	350	250	
30	480	340	420	300	
35	560	400	490	350	
40	640	455	560	400	
45	720	510	630	450	
50	805	570	700	500	
55	885	625	770	550	
60	965	685	840	600	
65	1045	740	910	650	
70	1125	795	980	700	



Where The Median Is Sufficiently Wide For The Design Vehicle To Pause In The Median (Vehicle Length Plus 6' Min.) The Clear Line Of Sight To The Right (d_R) Is Measured From The Vehicle Pause Location, i.e., Not From The Cross Road Stop Position; Distances d_r & d_m Do Not Apply.

INSET A



INSET B
* Lateral Offset For Restricted Conditions
Clear Zone For Nonrestricted Conditions

Median 30' or Less				
Design Speed (mph)	d_x (Ft.)	d_L (Ft.)	d_r (Ft.)	d_m (Ft.)
≤ 25	540	385	90	465
30	650	460	110	560
35	755	535	130	655
40	865	615	145	745
45	970	690	165	835
50	1080	765	185	930
55	1185	840	200	1025
60	1290	915	220	1115
65	1400	990	235	1210
70	1510	1070	255	1300

35'-50' Median				
Design Speed (mph)	d_x (Ft.)	d_L (Ft.)	d_r (Ft.)	d_m (Ft.)
≤ 25	585	415	80	520
30	700	495	95	625
35	815	580	115	725
40	930	660	130	825
45	1045	740	145	930
50	1165	825	160	1035
55	1280	905	175	1140
60	1395	990	190	1240
65	1510	1070	210	1340
70	1630	1155	225	1450

64' Median				
Design Speed (mph)	d (Ft.)	d_L (Ft.)	d_r (Ft.)	d_m (Ft.)
≤ 25	610	435	75	550
30	735	520	90	665
35	900	640	110	815
40	980	695	120	885
45	1100	780	135	995
50	1220	865	150	1100
55	1345	955	160	1215
60	1465	1040	175	1320
65	1590	1125	190	1435
70	1710	1210	205	1545

Combined Vehicles

Vehicle Type	Vehicle Length (Ft.)
Passenger (P)	19
Single Unit (SU)	30
Large School Bus	40
WB-40	45.5
WB-62FL	73.5

NOTES FOR 6-LANE DIVIDED ROADWAY

1. See Figure 212.11.1 for origin of clear sight line on the minor road.
2. Values shown in the tables are the governing (controlling) sight distances calculated based on 'AASHTO Case B - Intersection with Stop Control on the Minor Road.'

NOT TO SCALE

SIGHT DISTANCES (d), (d_V) & (d_X) AND RELATED DISTANCES (d_L, d_r, d_m & d_{rL}) (FEET)

LEGEND

Areas Free Of Sight Obstructions

EXHIBIT 212-7
01/01/2025



GENERAL NOTES

1. A Soil Tracking Prevention Device (STPD) shall be constructed at locations designated by the engineer for points of egress from unstabilized areas of the project to public roads where off-site tracking of mud could occur. Traffic from unstabilized areas of the construction project shall be directed thru a STPD. Barriers, flagging, or other positive means shall be used as required to limit and direct vehicular egress across the STPD.
2. The Contractor may propose an alternative technique to minimize off-site tracking of sediment. The alternative must be reviewed and approved by the Engineer prior to its use.
3. All materials spilled, dropped, or tracked onto public roads (including the STPD aggregate and construction mud) shall be removed daily, or more frequently if so directed by the Engineer.
4. Aggregates shall be as described in Section 901 excluding 901-2.3. Aggregates shall be FDOT size #1. If this size is not available, the next available smaller size aggregate may be substituted with the approval of the Engineer. Sizes containing excessive small aggregate will track off the project and are unsuitable.
5. The sediment pit should provide a retention volume of 3600 cubic feet/acre of surface area draining to the pit. When the STPD is isolated from other drainage areas, the following pit volumes will satisfy this requirement:
   15' x 50'=100 ft.³ 30' x 50'=200 ft.³
   As an option to the sediment pit, the width of the swale bottom can be increased to obtain the volume. When the sediment pit or swale volume has been reduced to one half, it shall be cleaned. When a swale is used, synthetic bales or silt fence shall be placed along the entire length.
6. The swale ditch draining the STPD shall have a 0.02% minimum and a 1.0% maximum grade along the STPD and to the sediment pit.
7. Mitered end sections are not required when the sidedrain pipe satisfies the clear zone requirements.
8. The STPD shall be maintained in a condition that will allow it to perform its function. To prevent off-site tracking, the STPD shall be rinsed (daily when in use) to move accumulated mud downward thru the stone. Additional stabilization of the vehicular route leading to the STPD may be required to limit the mud tracked.
9. A STPD shall be paid for under the contract unit price for Soil Tracking Prevention Device, EA. The unit price shall constitute full compensation for construction, maintenance, replacement of materials, removal, and restoration of the area utilized for the STPD; including but not limited to excavation, grading, temporary pipe (including MES when required), filter fabric, aggregate, paved turnout (including asphalt and base construction), ditch stabilization, approach route stabilization, sediment removal and disposal, water, rinsing and cleaning of the STPD and cleaning of public roads, grassing and sod. Synthetic Bale or Bale Type Barrier shall be paid for under the contract unit price for Synthetic Bales, LF. Silt fence shall be paid for under the contract unit price for Staked Silt Fence, LF.
10. The nominal size of a standard STPD is 15' x 50' unless otherwise shown in the plans. If the volume of entering and existing vehicles warrant, a 30' width STPD may be used if approved by the Engineer. When a double width (30') STPD is used, the pay quantity shall be 2 for each location.

2010 FDOT Design Standards	Last Revision 07/01/07	Sheet No. 1 of 1
SOIL TRACKING PREVENTION DEVICE TYPE A		Index No. 106



The Intent Of This Standard Is To Provide A Window With Vertical Limits Of Not Less Than 5' Above And 1'-6" Below The Sight Line Datum, And Horizontal Limits Defined By The Limits Of Clear Sight.

PICTORIAL

WINDOW DETAIL



SILT SCREEN
N.T.S.

NOTE:
THE EROSION BARRIER, AS SHOWN, IS NOT TO BE CONSTRUED TO MEAN THAT IT IS ALL THAT MAY BE REQUIRED. THE CONTRACTOR IS TO TAKE WHATEVER MEASURES NECESSARY TO CONTROL EROSION THROUGHOUT THE PROJECT. EROSION CONTROL WILL BE INSTALLED PRIOR TO LAND CLEARING AND SHALL REMAIN IN PLACE UNTIL THE AREA IS STABILIZED. (SEE OTHER EROSION AND TURBIDITY NOTES ON THE GENERAL NOTES SHEET OF THIS PLAN.)



HAY BALE
N.T.S.

EROSION CONTROL DETAILS
EITHER METHOD OR A COMBINATION OF BOTH IS ACCEPTABLE

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY
	REVISIONS	

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN No. 33133 STATE OF FLORIDA PROFESSIONAL ENGINEER

DATE:
DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

DRAINAGE DETAILS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE DD	SHEET 14 OF 21 SHEETS



TABLE 3 HORIZONTAL WALL REINFORCING SCHEDULE				
WALL DEPTH	SCHEDULE	AREA (in²/ft.)	MAX. SPACING	
			BARS	WWR
0' - 5'	A12	0.20	12"	8"
0' - 7.5'	A6	0.20	6"	5"
7.5' - 10'	B5.5	0.24	5½"	5"
10' - 15'	C6.5	0.37	6½"	6"

NOTES:

1. Grate, Concrete Apron, and Sod not shown on structure detail.
2. See Sheet 8, 9, and 10 for Concrete Apron and Sodded Area details.

STEEL GRATE DETAIL

(Approx. 215 lbs. - See Sheet 7 For Cast Iron Grates)

DIMENSIONAL AND REINFORCING DETAILS

TYPE E - DIMENSIONAL, REINFORCING, AND STEEL GRATE DETAILS

9/13/2024 7:48:17 AM

LAST REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	DITCH BOTTOM INLET TYPES C, D, E, AND H	INDEX	SHEET
11/01/20	REVISION			425-052	4 of 14



SPECIAL TOP SLAB





ALTERNATE A NOTES:

1. Rotate #4 Bars as required to maintain cover.
2. Construct the top or riser of the structure according the top slab to the "Special Top Slab" details, when the inside diameter of a round structure is not more than 1'-6" larger than the opening in the riser or top slab.
3. Alternate A slab reinforcing not applicable for Type A, B, C, D & E Ditch Bottom Inlets or Type S & V Gutter Inlets. See Indexes 425-040, 425-041, 425-050, 425-051, and 425-052.





DIMENSIONAL AND REINFORCING DETAILS

9/13/2024 7:48:40 AM

LAST REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	STRUCTURE BOTTOMS TYPE J AND P	INDEX	SHEET
11/01/20	REVISION			425-010	2 of 4

NOTES:

1. Steel Grates are required on inlets with traversable slots and on Inlets where bicycle traffic is anticipated.
2. Cast Iron Grates are not permitted on Inlet Type D.



CAST IRON GRATE DETAILS

9/13/2024 7:49:48 AM

LAST REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	DITCH BOTTOM INLET TYPES C, D, E, AND H	INDEX	SHEET
11/01/20	REVISION			425-052	7 of 14











ROUND CONCRETE PIPE

(Elliptical Pipe Similar)

NOTE: See Table 1 on Sheet 3 for Dimensions and Quantities.

SINGLE AND MULTIPLE CONCRETE PIPE

9/13/2024 7:58:20 AM

LAST REVISION	DESCRIPTION:	FDOT FY 2025-26 STANDARD PLANS	CROSS DRAIN MITERED END SECTION	INDEX	SHEET
11/01/19	REVISION			430-021	2 of 6

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY
	REVISIONS	

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
DAVID G. FUXAN No. 33133 STATE OF FLORIDA PROFESSIONAL ENGINEER
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194
DATE:
DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

DRAINAGE DETAILS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE DD	SHEET 15 OF 21 SHEETS



PLAN VIEW

END VIEW



SECTION A-A'

16'x 8' JUNCTION BOX & CONFLICT STRUCTURE

CREATED _____ REVISED _____	WATER AND STORM WATER CONFLICT STRUCTURE DETAIL MODIFIED	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
	PASCO COUNTY UTILITIES	DETAIL G20

BP-3A NOTE: DRAINAGE STRUCTURE #BP-3A WILL BE RECTANGULAR, NOT CIRCULAR

NOTES:

1. BOA TAPE OR WRAPIDSEAL SHALL BE USED ON ALL JOINTS, CASTINGS, AND RISER RINGS.
2. BOA TAPE OR WRAPIDSEAL SHALL BE USED IN ACCORDANCE WITH MFG RECOMMENDATIONS.
3. LIFT HOLES SHALL NOT PENETRATE WALLS.
4. PRECAST CONCRETE SHALL ATTAIN A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI AT 28 DAYS.
5. EXTERIOR AND INTERIOR SHALL RECEIVE 2 COATS OF COAL TAR EPOXY APPLIED AT THE RATE SPECIFIED IN THE PASCO COUNTY SPECIFICATIONS FOR DESIGN AND CONSTRUCTION OF WATER, WASTEWATER,AND RECLAIMED WATER FACILITIES.

CARRIER PIPE (INCHES)	CASING PIPE (INCHES)	CASING WALL THICKNESS (INCHES)
4	12	5/16
6	16	5/16
8	16	5/16
10	24	3/8
12	24	3/8
16	30	1/2
20	36	1/2
24	42	1/2
30	48	1/2
36	54	5/8
42	60	5/8
48	66	5/8

CREATED _____ REVISED _____ _____ NOV 2019	WATER AND STORM WATER CONFLICT STRUCTURE NOTES	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
	PASCO COUNTY UTILITIES	DETAIL G20A

NOTES

RENDERING

CANOPY AT PARKING FIELD

N

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY
	REVISIONS	

Engineering Business Certificate of Authorization No.: 26548
Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194
DATE: _____
DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

DRAINAGE DETAILS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE DD	SHEET 16 OF 21 SHEETS



C1 TRASH ENCLOSURE - SOUTHEAST
1/4" = 1'-0"

C2 TRASH ENCLOSURE - NORTHEAST
1/4" = 1'-0"



B1 TRASH ENCLOSURE - NORTHWEST
1/4" = 1'-0"



B2 TRASH ENCLOSURE - SOUTHWEST
1/4" = 1'-0"



B4 TRASH GATE CONNECTION DETAIL
3" = 1'-0"



A1 TRASH ENCLOSURE PLAN
1/4" = 1'-0"



A3 TRASH ENCLOSURE CAP PLAN
1/4" = 1'-0"



A4 TRASH ENCLOSURE WALL SECTION
3/4" = 1'-0"



A5 TRASH GATE POST DETAIL
3/4" = 1'-0"



A6 SLEEVED BOLLARD DETAIL
3/4" = 1'-0"

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY

REVISIONS

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

DUMPSTER ENCLOSURE DETAILS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE DD2	SHEET 17 OF 21 SHEETS

WETLAND
CONSERVATION AREA
CATEGORY I

MAJOR
TENANT A
BUILDING 100
35,518 SF
FF 56.00
ONE STORY

SHOPS - BLDG. 150
10,416 SF
FF 56.00
ONE STORY

SHOPS - BLDG. 200
16,017 SF
FF EL 56.00
ONE STORY

SHOPS - BLDG. 300
14,017 SF
FF 56.00
ONE STORY

MAJOR TENANT B
BLDG 400
84,500 SF
FF 56.70
2-STORIES
45' MAX. HT.

BRUCE B. DOWNS BLVD.
(County Road 581)
200' Right-of-Way
Asphalt Pavement

ARONWOOD BLVD.
Right-of-Way Varies

MH C2
TOP=55.30
INV.=50.02

MH C1
TOP=54.20
INV. (W)=49.76
INV. (S)=49.71

MH A1
TOP=53.30
INV.=47.63

MH A2
TOP=54.75
INV. (S&W)=48.12
INV. (N)=48.09

MH A3
TOP=56.00
INV.=48.30

MH B1
TOP=55.00
INV. (N&S)=49.52
INV. (E)=49.47

MH B2
TOP=54.50
INV. (W)=49.84
INV. (N)=49.79

MH B3
TOP=54.50
INV. (S)=50.43
INV. (E)=50.38

MH B4
TOP=54.40
INV. (W)=51.74
INV. (N)=51.69

MH B5
TOP=55.10
INV.=52.56

EX. 8" SAN

EX. 10" SAN

10" SAN

10" SANITARY SEWER @ 0.28%

8" SANITARY SEWER @ 0.40%

8" FIRE MAIN

4" WATER MAIN

4" POTABLE WATER MAIN

4" BLUE DR18 C900 PVC POTABLE WATER MAIN

8" C900 DR14 PVC FIRE MAIN

FIRE HYDRANT

FDC WITH 4" FIRE MAIN

2" BLOW-OFF 2" GATE VALVE

GREASE TRAP

(2)1500 GALLON GREASE TRAPS

(2) GREASE TRAPS

GAS METER

ICV

EXISTING IRRIGATION WELL AND 2" DIA. TANK TO REMAIN

EXISTING FIRE HYDRANT

EXISTING 16" WATER MAIN

SUBMIT SHOP DRAWINGS FOR SANITARY SEWER CROSSING OF DRAINAGE STORAGE VAULTS

15' Utility Easement
PB. 30, Pgs. 78-82

10' SANITARY SEWER @ 0.28%

SWFWL

WSB25

TRAFFIC

CWS

45 46 47 48 49 50 51 52

Hydrant Inspection: 1/31/2025

OBJECTID	380848
Asset ID	1677048
Clear of Obstructions	
Hydrant At Proper Level	
Nozzles/Caps Greased And Operable	
Flushed Hydrant	
Water Ran Clear	
Stem Operates Properly	
Main Valve Operates Properly	
Drain Valves Operate Properly	
Nozzles/Stem/Flange Operate Properly	
Painted Hydrant	
Top color Changed	
Top Color Changed To	
Located & Painted Values	
Reflectors Installed Properly	
Branch Valve Broken	
Branch Valve	
Valve Box	
Guards Properly Installed	
Low Water Pressure	
Concrete Hydrant Pad	
Hydrant Removed From Service	
Review Hydrant for Possible Replacement	
Does The Hydrant Need To Be Relocated	
At the time of this inspection, I certify that the hydrant was inspected based on the most current inspection process, which is consistent with AWWA M-17.	Yes
Date and Time Flowed	1/31/2025
Static Pressure	60.00
Flow	42.00
Gallons Per Minute	1,087.00
Residual	56.00
CC Flow	3,769.00
Top color	Blue

100 50 0 50 100

SCALE: 1" = 50'

Pasco County Utility Notes:

1. *Pasco County shall not own or maintain any water lines, sewer lines, or facilities constructed on private property.*
2. *All materials and labor shall meet the specifications required by the county. All construction shall be performed under the inspection of the county and in strict compliance with the standards of the county design standards.*
3. *All newly installed water distribution mains and service laterals shall be color coded blue.*
4. *All newly installed force mains and gravity lines shall be color coded green.*
5. *Connections to the County's system shall be made by wet tap. Wet taps shall be performed exclusively by Pasco County Utilities at the developer's expense. Excavation, backfill, and surface restoration shall be the contractor's responsibility.*
6. *Contractor's Responsibilities regarding wet taps two inches and larger shall be as follows:*

   2" Only: The excavated trench must be dry or the trench will require rock and a pump to be in place. The minimum distance from the face of the valve to the wall of the trench is to be six feet. The County will provide the tapping saddle, corporation stop, stainless steel nipple, and iron body valve.

   3" and Larger: The contractor will supply a tapping saddle being epoxy coated, a tapping valvewith mechanical joint and the equipment to provide, and conduct a pressure test. County personnel will witness the pressure test which must be at 150 psi for duration of thirty minutes.

   The contractor is responsible for the excavation before any County personnel will enter an excavated area. If the trench is four feet in depth or deeper, it will require a trench box or sloping, and a ladder according to Occupational Safety and Health Administration (OSHA) standards.

   The tapping valve will require a blocking device made of suitable material or device. This blocking device or material will be placed under the valve and remain in place until the tap machine is removed and the tap is completed.

WATER MAIN POC #1
EXISTING WATER SERVICE EASEMENT WITH 4" POTABLE WATER MAIN WITH EXISTING 2" METER 4" POTABLE WATER MAIN WITH PROPOSED 1 1/2" METER EXISTING 6" DDCV WITH PROPOSED 8" FIRE MAIN (SEE SHEET 19 FOR DETAIL)

WATER MAIN POC #2
PROPOSED 4" POTABLE WATER MAIN WITH 2" METER, 6" DDCV WITH PROPOSED 8" FIRE MAIN (SEE DETAIL ON SHEET 19)

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY
	REVISIONS	

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN No. 33133 STATE OF FLORIDA PROFESSIONAL ENGINEER

DATE:

DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

WATER AND SEWER PLAN

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE WSP	SHEET 18 OF 21 SHEETS



SECTION

MATERIALS		
ITEM	QUANT.	DESCRIPTION
1	1	DOUBLE CHECK WITH DETECTOR ASSEMBLY
2	2	BEND, 90° FLANGE x FLANGE
3	2	SPOOL PIECE FLG. x PE. D.I.P.
4	2	BEND, 90° M.J. x M.J.
5	4	RESTRAINED JOINT MJ (MEGALUG OR EQUAL)
6	2	VALVE, GATE FLG. x FLG. RESILIENT WEDGE O.S. & Y.
7	2	SUPPORT (AS NEEDED)
8	1	CONCRETE SLAB (6" THICK - 42" WIDE MIN.)
9	1	AMR (BADGER) ORION READING SYSTEM
10	2	ADJ. PIPE SUPPORTS - ANVIL FIG. 265 W/ 63T STANCHION & BASE PLATE
11	1	ISOLATION VALVE AND VALVE BOX, SLIP TYPE AS PER PCU STANDARD DETAIL G-5 LOCATED AT BRANCH NEAREST TO COUNTY WATER MAIN.

CREATED	FEB 2003	DOUBLE CHECK WITH DETECTOR ASSEMBLY FOR FIRE SERVICE LINES (3", 4", 6", 8", 12")	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
REVISED	MAY 2021		
		PASCO COUNTY UTILITIES	DETAIL W7



CREATED	NOV 2020	AMR METER SERVICE INSTALLATION 1-1/2" or 2"	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
REVISED	MAY 2021		
		PASCO COUNTY UTILITIES	DETAIL G14



NOTE:
IF THE METER ASSEMBLY IS LOCATED WITHIN A TRAFFIC / VEHICLE AREA (PARKING LOT, DRIVEWAY, OR WITHIN 15 FEET OF EDGE OF PAVEMENT OR BACK OF CURB), ABOVE GROUND METERS UP TO 2 INCHES SHALL HAVE A MINIMUM OF FOUR TRAFFIC BOLLARD PROTECTION POSTS AND FOR ABOVE GROUND METERS 3 INCHES AND LARGER A MINIMUM OF 6 TRAFFIC BOLLARDS ARE REQUIRED.

CREATED	FEB 2021	BOLLARD POST DETAIL	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
REVISED	MAY 2021		
		PASCO COUNTY UTILITIES	DETAIL G18



MATERIALS		
ITEM	QUANT.	DESCRIPTION
1	2	BACKFLOW PREVENTER (BFP) ASSY., REDUCED PRESSURE ZONE (RPZ) AND 2 BALL VALVES-BRASS
2	12	6" NIPPLES -BRASS OR S.S.
3	4	UNION - BRASS OR S.S.
4	4	90° ELBOWS - BRASS OR S.S.
5	4	4" BOLLARDS - SEE STANDARD DETAIL G18
6	2	RISER - BRASS OR S.S.
7	2	TEES - BRASS OR S.S.
8	*	CONCRETE SLAB 4" THICK W/ 6"x6" 10/10 W.W.F. OR FIBERMESH REINFORCING

CREATED	FEB 2021	REDUCED PRESSURE BACKFLOW PREVENTER ASSY. PARALLEL INSTALLATION (3/4", 1", 1-1/2", 2")	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
REVISED	MAY 2021		
		PASCO COUNTY UTILITIES	DETAIL W9



WATER MAIN POC #1

Scale: 1"=10'



WATER MAIN POC #2

Scale: 1"=10'



PERPENDICULAR TO THE MAIN

MATERIALS		
ITEM	QUANT.	DESCRIPTION
1	1	FIRE HYDRANT (5 1/4" VALVE MIN.), PAINTED YELLOW
2	*	RESERVED
3	1	VALVE BOX, SLIP TYPE
4	1	6" VALVE, GATE, M.J. RESILIENT WEDGE, N.R.S.
5	1	ANCHOR TEE, M.J.
6	*	6" RESTRAINED JOINT M.J. (MEGALUG OR EQUAL)
7	*	VALVE EXTENSION ROD, AS NECESSARY (3' MAX. BELOW GRADE)
8	*	6" 90° BEND, D.I., RESTRAINED

NOTES:
1. MINIMUM CLEARANCE OF 18" FROM C/L OF STEAMER NOZZLE TO FINAL GRADE, TO BE ADJUSTED BY CONTRACTOR.
2. ADD REFLECTIVE PAVEMENT MARKER (RPM, BLUE/BLUE) IN CENTER OF LANE IMMEDIATELY ADJACENT TO HYDRANT.
3. A 3-FT CLEAR ZONE SURROUNDING THE HYDRANT SHALL BE FREE OF ANY TREES, SHRUBS, AND DRIVEWAYS.
4. HYDRANT CAPS SHALL BE COLOR CODED BASED ON FLOW RATES:
   - BELOW 500 GPM: RED
   - 500–1,000 GPM: ORANGE
   - 1,000–1,500 GPM: GREEN
   - ABOVE–1,500 GPM: BLUE
5. THE FOLLOWING FIRE HYDRANTS ARE ACCEPTABLE – AMERICAN FLOW B-84-B; KENNEDY K-81 OR EQUAL

CREATED	FEB 2003	STANDARD FIRE HYDRANT CONFIGURATION	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
REVISED	SEPT 2014		
	AUG 2015		
	FEB 2020	PASCO COUNTY UTILITIES	DETAIL W13



PARALLEL TO THE MAIN

MATERIALS		
ITEM	QUANT.	DESCRIPTION
1	1	FIRE HYDRANT (5 1/4" VALVE MIN.) BODY PAINTED YELLOW
2	*	6" DIA. PIPE, P.V.C. (DR-14) MAX 20' LENGTH
3	1	VALVE BOX, SLIP TYPE
4	1	6" VALVE, GATE, M.J. RESILIENT WEDGE, N.R.S.
5	1	MJ ANCHOR TEE
6	*	6" RESTRAINED JOINT M.J. (MEGALUG OR EQUAL)
7	1	6" 90° BEND M.J. D.I. RESTRAINED
8	*	VALVE EXTENSION ROD, AS NECESSARY (3' MAX. BELOW GRADE)

CREATED	MAY 2021	FIRE HYDRANT CONFIGURATION (SPACE-CONSTRAINED)	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
REVISED			
		PASCO COUNTY UTILITIES	DETAIL W14

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY
	REVISIONS	

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

POTABLE WATER SYSTEM DETAILS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE WD	SHEET 19 OF 21 SHEETS



NOTES:
1. ALL CONCRETE SHALL BE TYP II CEMENT, MEETING LATEST ASTM REQUIRMENTS AND PROVIDED WITHON LABORATORY CERTIFICATION.
2. BOA TAPE MUST BE USED IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
3. THE TYPE OF INTERIOR LINING USED SHALL BE QUADEX GEOKRETE ON ALL STRUCTURES TO BE LINED.
4. A FORCE MAIN CONNECTION REQUIRES THE RECEIVING MANHOLE AND THE FOUR DOWNSTREAM & FOUR UPSTREAM MANHOLES TO BE LINED. AT PUMP STATIONS THE "KING" MANHOLE AND 4 UPSTREAM MANHOLES (EACH INVERT) SHALL BE LINED.
5. PASCO COUNTY MAY REQUIRE ADDITIONAL MANHOLES TO BE LINED BASED ON MANHOLE SPACING.
6. PASCO COUNTY SHALL HAVE THE OPTION OF REQUIRING A NEGATIVE PRESSURE TEST PER ASTM C-1244.
7. LIFT HOLES MUST NOT PENETRATE THE WALLS.
8. PRECAST CONCRETE SHALL ATTAIN A MINIMUM COMPRESSIVE STRENGTH OF 4,000 PSI AT 28 DAYS.
9. USE OF ECCENTRIC CONES REQUIRES SPECIAL APPROVAL.
10. EXTERIOR AND INTERIOR COATING, CONSEAL CS-55 OR PROTECH EW-1 AQUAPOXY OR APPROVED EQUAL AT THE MINIMUM RATE /THICKNESS RECOMMENDED BY THE MANUFACTURER COAL TAR IS NOT ALLOWED
11. MANHOLE W/ CONNECTION SHALL HAVE 24 HR HYDROSTATIC LEAK TEST.
12. ALL LINED MANHOLES SHALL HAVE COMPOSITE FRAME AND COVER AS MANUFACTURED BY CAP OR EQUAL. COMPOSITE FRAMES AND COVERS NOT TO BE PLACED ON THE PAVEMENT AREA

CREATED FEB 2021 REVISED MAY 2021	STANDARD MANHOLE	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
	PASCO COUNTY UTILITIES	DETAIL S1



SECTION

NOTES:
CONTRACTOR SHALL MAKE, ON A CLEAN SET OF PLANS, THE FINAL STATIONING OR DISTANCE AND DIRECTION FROM MANHOLE OF EACH SERVICE LATERAL AND THEN GIVE TO ENGINEER FOR RECORD PURPOSES.

PROVIDE 2" x 4" PRESSURE TREATED WOOD MARKER STAKE AT ALL SANITARY SERVICES (INCLUDE IN PIPE PRICE), TOP OF STAKE TO BE PAINTED WITH GREEN PAINT.

THE MINIMUM DIAMETER OF SINGLE SERVICE LATERALS SHALL BE 4".THE MINIMUM DIAMETER OF DOUBLE SERVICE LATERALS SHALL BE 6".

REFER TO STANDARD PCU DETAIL G-9 FOR CLEARANCE CRITERIA.

SEWER SERVICES MUST NOT BE LOCATED IN REAR YARDS.

CREATED FEB 2021 REVISED MAY 2021	SANITARY SEWER LATERAL CONNECTION	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
	PASCO COUNTY UTILITIES	DETAIL S4



CREATED FEB 2021 REVISED MAY 2021	SANITARY SEWER – SINGLE WYE CONNECTION AND TYPICAL CLEAN–OUT	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
	PASCO COUNTY UTILITIES	DETAIL S6



NTS

CREATED FEB 2021 REVISED MAY 2021	SANITARY SEWER – DOUBLE WYE CONNECTION AND TYPICAL CLEAN–OUT	PROVIDED FOR INFORMATIONAL PURPOSES ONLY. NO MODIFICATIONS WITHOUT WRITTEN PCU APPROVAL
	PASCO COUNTY UTILITIES	DETAIL S7

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY
	REVISIONS	

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
No. 33133
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

SANITARY SEWER SYSTEM DETAILS

JOB NO. 2025-MP2-01	MEADOW POINTE TRACT 2
DESIGN FUXAN	
DRAWN MIDDLETON	PREPARED FOR: SJC Ventures
DATE 2-9-2025	Elevations based on North American Vertical Datum 1988 (NAVD 88) Conversion from NAVD 88 to NGVD 29 = +0.82 Feet
FILE SD	SHEET 20 OF 21 SHEETS

SCALE: 1" = 50'

SWFWMD MODEL DATA
100 YR DHW = 54.57
25 YR DHW = 53.54
2.33 YR DHW = 49.32

RETAINING WALL
REFER TO ARCHITECTURAL PLANS FOR DETAILS

GENERATOR WITH FUEL TANK SLAB EL. 55.50

WETLAND CONSERVATION AREA
CATEGORY I
SH 48.67

SWFWMD MODEL DATA
100 YR DHW = 54.60
25 YR DHW = 53.57
2.33 YR DHW = 50.30

REFER TO SHEET 7 FOR EXISTING CONTROL STRUCTURE MODIFICATIONS

PROPOSED SUMP WITH RETAINING WALL
REFER TO ARCHITECTURAL PLANS FOR DETAILS
TOP OF WALL 52.50
SUMP EL. 48.00

Existing Endwall Inv.=46.17'

Existing Control Structure
Skimmer Elev.=51.51'
Conc. Wall Top Elev.=50.09'

EXISTING DETENTION POND
25 YR DHW = 51.22
DLW = 50.17
NW = 48.67

RETAINING WALL
REFER TO ARCHITECTURAL PLANS FOR DETAILS

EXISTING DOUBLE 48" RCP'S

15' Utility Easement
PB. 30, Pgs. 78–82

EXISTING DETENTION POND
25 YR DHW = 53.12
DLW = 52.12
NW = 51.47

Existing Control Structure

EX. 36" RCP

INV. 51.70
POOL DECK

REFER TO ARCHITECTURAL PLANS FOR POOL DECK DRAINS

MAJOR TENANT A
BUILDING 100
35,518 SF
FF 56.00
ONE STORY

SHOPS - BLDG. 150
10,416 SF
FF 56.00
ONE STORY

MAJOR TENANT B
BLDG 400
84,500 SF
FF 56.70
2-STORIES
45' MAX. HT.

SHOPS - BLDG. 200
16,017 SF
FF EL 56.00
ONE STORY

SHOPS - BLDG. 300
14,017 SF
FF 56.00
ONE STORY

15.13 ACRES TRIBUTARY TO DRAINAGE VAULT

HEAVY DUTY TRENCH DRAIN GRATE EL. 52.00

TRUCK DOCKS

TRASH COMPACTORS

DUMPSTERS

DUMPSTER W/ ENCLOSURE

Elev=48.72'
TOW 08-15-24

Elev=50.02'
TOW 08-20-24

CONNECT ROOF DRAINS TO 12"

HC SPACES FLUSH WITH SIDEWALK

7' SIDEWALK

16'X 8' JUNCTION BOX/ CONFLICT STRUCTURE

ICV

Headwall

24"x 38"

30"x 68"

COVERED PARKING (SEE DETAIL ON SHEET 6)

PROPOSED MONUMENT SIGN

TYPE C VAULT INLET TOP (TYP.)

EXISTING SIDEWALK TO REMAIN

EXISTING TYPE F CURB

PROPOSED PAVEMENT AND CURB

3' CONCRETE TRAFFIC SEPARATOR

REPLACE INLET TOP WITH MANHOLE TOP EL 55.70

EXISTING LEFT TURN LANE

PROPOSED MEDIAN PAVEMENT

ARONWOOD BLVD.
Right-of-Way Varies

BRUCE B. DOWNS BLVD.
(County Road 581)
200' Right-of-Way
Asphalt Pavement

FJB

TRAFFIC

CWS

POOL DECK

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY

REVISIONS

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

STATE OF FLORIDA — DAVID G. FUXAN — No. 33133 — REGISTERED PROFESSIONAL ENGINEER

DATE:

DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

DRAINAGE AREA MAP

JOB NO. 2025-MP2-01

MEADOW POINTE TRACT 2

DESIGN FUXAN

DRAWN MIDDLETON

PREPARED FOR: SJC Ventures

DATE 2-9-2025

Elevations based on North American Vertical Datum 1988 (NAVD 88)
Conversion from NAVD 88 to NGVD 29 = +0.82 Feet

FILE DRA

SHEET 21 OF 21 SHEETS

PROPERTY OWNERSHIP AND EASEMENT MAP

MEADOW POINTE TRACT 2

SCALE: 1" = 50'

POINT OF COMMENCEMENT
Northwest corner of Section 31, Township 26 South, Range 20 East

S89°58'03"E 101.26'

Northwest corner of the Southwest 1/4 of Section 31

S00°30'11"W 2643.60'

North boundary of Section 31

NW 1/4 OF SECTION 31-26-20
SW 1/4 OF SECTION 31-26-20

S00°30'15"W

POINT OF BEGINNING
FCM 4X4 LB148 PRM

S75°52'42"E 20.58'

2753.46'

2916.54'

Meadow Pointe Community Development District
Parcel ID:
31-26-20-0000-00100-00D2

UNPLATTED TRACT "D"

MEADOW POINTE PARCEL 3 UNIT 2 PLAT BOOK 30, PAGES 78-82

Corner Not Found or Set (Covered by Derbies)

FCM 4X4 LB148 PRM (0.10'N)

FCM 4X4 LB148 PRM (0.26'N)

FCM 4X4 LB148 PRM (0.19'N)

FCM 4X4 LB148 PRM (0.16'N)

FCM 4X4 LB148 PRM (0.18'N)

FCM 4X4 LB148 PRM (0.21'N&0.25'W)

FCM 4X4 LB148 PRM (0.22'N)

36.61'

L1 L2 L3 L4 L5 L6 L7 L8 L9 L10 L11 L12 L13 L14 L15 L16 L17 L18 L19 L20 L21 L22 L23 L24 L25 L26 L27 L28

45 46 47 48 49 51 52

PARCEL 3
Private Financing Alternatives
O.R. 9438, Pg. 3655

TRACT "B"

POND PORTION OF DRAINAGE EASEMENT TO BE REPLACED

20.0'

172.04'

20' Right-of-Way For County Road No. 581 O.R. 7996 Pg. 1076

18' Perpetual Slope Easement O.R. 7867 Pg. 1452
TO REMAIN

15' Teco Easement O.R. 7875, Pg. 1700
TO BE REPLACED

42' Permanent Drainage Easement O.R. 8269 Pg. 1276
TO REMAIN

15' Utility Easement PB. 30, Pgs. 78-82
TO REMAIN

20' Landscape Buffer/Easement PB. 68, Pg. 99
TO REMAIN

Southerly boundary of Meadow Pointe Parcel 3, Unit 3

FCM 4X4 NO ID

FMGD LB148

FMGD PLS 2012

UNPLATTED
Pasco County Facilities Management Dept.
O.R. 3072, Pg. 0073

518.63'

54.30'

15' Teco Easement O.R. 7875, Pg. 1700
TO BE REPLACED

Temporary Drainage Easement O.R. 8269 Pg. 1276
TO BE VACATED

15' Permanent Drainage Easement O.R. 8269 Pg. 1276
TO REMAIN

10' Landscape Buffer PB. 68, Pg. 99
TO REMAIN

EXAL LLC
O.R. 9818, Pg. 3355

UNPLATTED
NOT INCLUDED
PARCEL 2

20' Additional Right-of-Way For Bruce B. Downs O.R. 7883 Pg. 963

320.34'

10' Teco Easement O.R. 7875, Pg. 1698
TO BE REPLACED

24' Access Easement PB. 68, Pg. 99
TO BE REPLACED

MAJOR TENANT B OWNERSHIP

PROPOSED PROPERTY LINE

Private Financing Alternatives
O.R. 9438, Pg. 3655

AREA=13.835 ACRES±

PARCEL 4

MEADOW POINTE TRACT 2
PLAT BOOK 68, PAGES 99-103

37' Temporary Drainage Easement O.R. 8269 Pg. 1276
TO BE VACATED

15' Permanent Drainage Easement O.R. 8269 Pg. 1276
TO REMAIN

15' Non-Exclusive Drainage Easement O.R. 8269 Pg. 1276
TO REMAIN

20' Landscape Buffer/Easement PB. 68, Pg. 99
TO REMAIN

Pasco County Facilities Management Dept.
O.R. 3072, Pg. 0073

SECTION 36-26-19
SECTION 31-26-20

(Basis of Bearings) S00°29'53"W 2654.79'

West boundary of Section 31

BRUCE B. DOWNS BOULEVARD
(County Road 581)
200' Right-of-Way
Asphalt Pavement

East Right-of-Way Line

SJC OWNERSHIP

TO REMAIN
18' Perpetual Slope Easement O.R. 7867 Pg. 1445

10' Teco Easement O.R. 7875, Pg. 1698
TO BE REPLACED

10' Teco Easement O.R. 7875, Pg. 1698
TO BE REPLACED

5.36.02'

FCM 4X4 LB148 PRM (0.20'N)

FCM 4X4 LB148 PRM (0.15'N)

15' Teco Easement O.R. 7875, Pg. 1700
TO BE REPLACED

PARCEL 1
Private Financing Alternatives
O.R. 9438, Pg. 3655

20' Right-of-Way For County Road No. 581 O.R. 7996 Pg. 1076

18' Perpetual Slope Easement O.R. 7867 Pg. 1452
TO REMAIN

236.35'

24' Access Easement PB. 68, Pg. 99
TO BE REPLACED

TO BE REDUCED TO 15' WIDTH

20' Landscape, Wall and Sidewalk Easement PB. 68, Pg. 99
TO REMAIN

C1

FCM 4X4 LB148 PRM (0.33'N)

FCM 4X4 LB148 PRM (0.21'N)

FCM 4X4 LB148 PRM (0.31'N)

Water Meter Easement PB. 68, Pg. 99
TO REMAIN

20' Landscape, Wall and Sidewalk Easement PB. 68, Pg. 99
TO REMAIN

FCM 4X4 LB148 PRM (0.12'N)

379.58'

Northerly Right-of-Way

ARONWOOD BOULEVARD
Right-of-Way Varies
Asphalt Pavement

C2 C3

FCM 4X4 PRM FLA REG 4498

FCM 4X4 LB148 PRM (0.11'N)
Clear Site Triangle

Pasco County / Hillsborough County

SECTION 31-26-20
SECTION 27-5-20

36 31 1 6

David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY
	REVISIONS	

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

DAVID G. FUXAN No. 33133 STATE OF FLORIDA PROFESSIONAL ENGINEER

DATE:

DAVID G. FUXAN P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

JOB NO.	2025-MP2-01
DESIGN	FUXAN
DRAWN	MIDDLETON
DATE	2-9-2025
FILE	POEM
PREPARED FOR:	SJC Ventures

Elevations based on North American Vertical Datum 1988 (NAVD 88)
Conversion from NAVD 88 to NGVD 29 = +0.82 Feet

SHEET 1 OF 1 SHEETS



David G. Fuxan, State of Florida Professional Engineer, Licence No. 33133
This item has been digitally signed and sealed by
David G. Fuxan, P.E. on the date indicated here.
Printed copies of this document are not considered signed and sealed,
and the signature must be verified on any electronic copies.

DATE	DESCRIPTION	BY

REVISIONS

Engineering Business Certificate of Authorization No.: 26548

Fuxan Engineering, Inc.
No. 33133
15018 Maurine Cove Ln.
Odessa, Florida 33556
Phone: 813-244-6194

STATE OF FLORIDA PROFESSIONAL ENGINEER

DATE:

DAVID G. FUXAN, P.E. NO. 33133
FLORIDA PROFESSIONAL ENGINEER

SHARED SITE COSTS MAP

MEADOW POINTE TRACT 2

JOB NO.	2025-MP2-01
DESIGN	FUXAN
DRAWN	MIDDLETON
DATE	2-9-2025
FILE	SSCM
PREPARED FOR:	SJC Ventures

Elevations based on North American Vertical Datum 1988 (NAVD 88)
Conversion from NAVD 88 to NGVD 29 = +0.82 Feet

SHEET 1 OF 1 SHEETS